




4501 W Highland
11-30-101-002






90 45 0 90 Feet



CHARTER TOWNSHIP OF HIGHLAND ZONING MAP

URSA 24-03
 SPR 24-03
 SCHOOL BELL
 CHILD CARE CENTER

-  OC Tax Parcel Stacked
- Zoning Districts**
-  ARR: Agricultural Rural Residential 5 acre
-  LV: Lakes and Villages
-  R1.5: Residential 1.5 acre
-  R3: Residential 3 acre
-  RM: Multiple Family
-  MH: Mobile Home Park
-  OS: Office Service
-  C-1: Local Commercial
-  C-2: General Commercial
-  HS: Highland Station
-  TR: Technology and Research
-  IM: Industrial Manufacturing





- Site Plan Review
- Rezoning
- Use Requiring Special Approval
- Land Division
- Land Division & Combination
- Road Profile
- Other

PLAN REVIEW APPLICATION

Highland Township Planning Department, 205 N. John St, Highland, Michigan 48357 (248) 887-3791 Ext. 2

Date Filed: _____ Fee: _____ Escrow: _____ Case Number: _____

NOTICE TO APPLICANT AND OWNER

BY SIGNING THIS APPLICATION, THE APPLICANT AND OWNER ACKNOWLEDGE ONE OR THE OTHER OR BOTH ARE RESPONSIBLE FOR ALL APPLICATION AND CONSULTANT FEES THAT ARISE OUT OF THE REVIEW OF THIS REQUEST THE OWNER ALSO AUTHORIZES THE TOWNSHIP TO PLACE A SIGN ON THE PROPERTY, IF NECESSARY, TO INFORM THE PUBLIC OF THE PENDING MATTER BEING REQUESTED.

REQUIRED COPIES OF PLANS

INITIAL REVIEW: 2 HARD COPIES OF PLANS AND .PDF COPY OF PLANS
 CONSULTANTS REVIEW OF APPROVED PLANS SUBJECT TO CONDITIONS: 5 COPIES AND .PDF COPY

1. APPLICANT INFORMATION

NAME: _____
 ADDRESS: _____

 PHONE: _____
 EMAIL: _____

OWNER INFORMATION

NAME: _____
 ADDRESS: _____

 PHONE: _____
 EMAIL: _____

2. PROPERTY INFORMATION

ADDRESS OR ADJACENT STREETS: _____
 LOT WIDTH: _____ LOT DEPTH: _____ LOT AREA: _____
 PARCEL IDENTIFICATION NUMBER(S): _____

3. PROJECT INFORMATION

PROJECT NAME: _____
 PRESENT ZONING: _____ PROPOSED ZONING: _____
 PRESENT USE: _____ PROPOSED USE: _____

APPLICANT

SIGNATURE: Marc Kasabasic
 PRINT NAME: _____

On the ___ day of _____, _____ before me, a Notary Public, personally appeared the above named person whose signature appears above, and who executed the foregoing instrument, and he/she acknowledged to me that he/she executed the same.

State Of Michigan
 County Of Oakland

Notary Public: _____

OWNER

SIGNATURE: Federica Kasabasic
 PRINT NAME: _____

On the ___ day of _____, _____ before me, a Notary Public, personally appeared the above named person whose signature appears above, and who executed the foregoing instrument, and he/she acknowledged to me that he/she executed the same.

State Of Michigan
 County Of Oakland

Notary Public: _____

• If there are Co-Applicants and/or Co-Owners associated with this property(ies) to be acted upon, please submit a Notarized Co-Applicant's and/or Co-owner's "Interest in Property Certificate" with this application. The person signing this cover sheet will be considered the official designee for the group and all correspondence will be addressed to this person.

• A notarized letter giving the Applicant authorization to represent the Owner is also permitted in lieu of a signature on this application. The person signing this cover sheet, however, will be considered the official designee for the Owner and all correspondence will be addressed to this person.

**HIGHLAND TOWNSHIP IMPACT ASSESSMENT
School Bell Childcare**

Prepared for:

**Property Owner
School of the Pines Inc. dba School Bell Childcare
Marc Kasabasic**

**Applicant
School of the Pines Inc. dba School Bell Childcare
Marc Kasabasic**

Prepared by:

Jared Prather, E.I.T.



3121 E. Grand River Howell, MI 48843
517.546.4836 fax 517.548.1670
www.bosseng.com

May 31st, 2024

DISCUSSION ITEMS

Name(s) and address(es) of person(s) responsible for preparation of the General Description and a brief statement of their qualifications.

Prepared by:

Jared Prather, E.I.T.
Project Engineer
Boss Engineering
3121 E Grand River
Howell, MI 48843

Prepared for:

Owner & Applicant:

School of the Pines Inc. dba School Bell Childcare / Marc Kasabasic
4501 W. Highland Road
Milford, MI 48380

General Site Description

The project site is on parcel #11-30-101-002 in Section 30, Highland Township, Oakland County, MI 48380.

The subject site is bordered:

- On the west by a large, open parcel 6.10 acres in size zoned Lake & Village (LV).
- On the north by the West Highland Road (M-59) MDOT Right of Way.
- On the east by a single-family residential parcel, 0.75 acres in size, zoned LV.
- On the southeast by Pommere Drive
- And on the south by a single-family residential parcel, 0.85 acres in size, zoned LV.

The subject site is an occupied parcel of land consisting of an operational day care center along West Highland Road with a driveway, paved parking lot, playground, fence separating the driveway from the playground, and wooded area in the east. Sanitary and water services are provided by existing onsite septic and well systems. The existing septic field and reserve septic field is on the southwest side of the playground and the well is on the northern edge of the parking lot. Along the southeastern property bend lies Pommere Drive (See the Existing Conditions Plan). The front of the property is a flat lawn space and the eastern half of the property has a moderately wooded area. There is currently one existing paved commercial drive approach from the north end of the subject property leading to the unstriped parking lot and gravel parking area from W Highland Road (M-59).

Natural Features

The parcel is developed. As described earlier, the property includes a day care building, a paved parking lot, and a playground. The day care center and playground occupy approximately the western half of the site with the paved parking lot in the middle of the site. The remaining eastern half of the site is moderately wooded with a collection of trees.

The site slopes from the center outwardly at 1-3% in all directions. The northern side of the parcel slopes toward W Highland Road (M-59) with slopes increasing from 2% to 6-10%, western side slopes toward the adjacent parcel field from 1-2% to 5-10%, eastern side sloping toward the adjacent property from 2% to 3-5%, and southern side sloping toward Pommere Drive from 2-3% to 10-20%. The site generally drains from the center to the north onto W Highland Road (M-59) with the remaining drainage following the site slopes.

The NRCS soils on the whole property are Fox Sandy Loam at 1-6% slope which is consistent with the general character of the slopes on the site.

Storm Water Management

Storm water will be managed onsite with the creation of a new storm water sewer network. The new school building, parking lot, and some of the modified playground area will be captured in catch basins and directed to the new underground detention system with a restricted discharge to the W Highland Road (M-59) MDOT right-of-way storm ditch and culvert through an overflow control structure. Detailed construction plans will be reviewed by the Township Engineer and the Soil Erosion Control plans will be reviewed and permit issued by the Livingston County Drain Commissioners office prior to construction commencing. Ongoing/periodic soil erosion inspections will occur per County requirements to ensure soil erosion is managed proactively.

Impact on Surrounding Land Use

The proposed special use will conform to existing development patterns and will not negatively impact adjacent properties with added lighting, noise, or air pollution. The proposed project seeks to expand the business operation of School Bell Childcare with the creation of a new schoolhouse building. The site development will comply with Township Ordinances and will meet the current Township, County, and State engineering standards. There will be minimal impact on surrounding land uses or development patterns as there will be no change to these uses. Additional lighting will be designed to illuminate the new schoolhouse building and parking lot and will not impact the adjacent residential homes.

Impact on Public Facilities and Services

The proposed updates to the existing site will not add any additional burden on the fire and police services. Fire trucks will use the M-59 right-of-way to access the site in case of a fire on either side of the site with an additional access behind the site from Pommere Drive. No hydrant coverage exists on the site. Refuse vehicles will have access to the onsite dumpster located at the southern end of the driveway to collect the garbage. The use increases the maximum overall school population to 96 students and 13 staff.

Impact on Public Utilities

Storm water will be detained onsite via the use of an underground detention system. Overall runoff along the northern end of the site toward W Highland Road (M-59) will be reduced below existing conditions. The storm water will be discharged at the restricted rate to the MDOT right-of-way culvert and ditch instead of the existing uncontrolled condition. Detailed construction plans would be reviewed by the Township Engineer and a Soil Erosion Control permit would be reviewed and issued by the Oakland County Drain Commissioner. Water & sanitary services will continue to be provided using the existing well and the existing and proposed septic systems onsite.

Storage or Handling of any Hazardous Materials

No storing or handling of any bulk hazardous materials is expected for this development.

Impact on Traffic and Pedestrians

A Trip Generation summary has been completed using the ITE 10th Edition Volume 2 manual and is included on the plans. The number of students will increase from 50 to 96 and would generate a maximum AM peak total of 75 trips and PM peak total of 76 trips from the arrival to the departure of the site. The entryway will be enlarged to 24 feet wide in conformance with the driveway width requirement along W Highland Road (M-59).

Special Provisions

A special land use permit application will be submitted with the site plan.

Description of all sources:

- Highland Township Zoning Ordinance and engineering standards
- Oakland County Drain Commissioner engineering standards
- NRCS Web Soil Survey
- Institute of Traffic Engineers (ITE) Trip General Manual, 10th Edition

GENERAL NOTES

- 1. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL REQUIRED TOWNSHIP, COUNTY, AND STATE OF MICHIGAN PERMITS.
2. A GRADING PERMIT FOR SOIL EROSION--SEDIMENTATION CONTROL SHALL BE OBTAINED FROM THE GOVERNING AGENCY PRIOR TO THE START OF CONSTRUCTION.
3. IF DUST PROBLEM OCCURS DURING CONSTRUCTION, CONTROL WILL BE PROVIDED BY AN APPLICATION OF WATER, EITHER BY SPRINKLER OR TANK TRUCK.
4. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH LOCAL MUNICIPAL STANDARDS AND SPECIFICATIONS.
5. PAVED SURFACES, WALKWAYS, SIGNS, LIGHTING AND OTHER STRUCTURES SHALL BE MAINTAINED IN A SAFE, ATTRACTIVE CONDITION AS ORIGINALLY DESIGNED AND CONSTRUCTED.
6. ALL BARRIER-FREE FEATURES SHALL BE CONSTRUCTED TO MEET ALL LOCAL, STATE AND A.D.A. REQUIREMENTS. WHERE EXISTING CONDITIONS AND/OR THE REQUIREMENTS OF THE PLANS WILL RESULT IN FINISHED CONDITIONS THAT DO NOT MEET ADA REQUIREMENTS, THE CONTRACTOR SHALL NOTIFY THE DESIGN ENGINEER PRIOR TO WORK COMMENCING.
7. ANY DISCREPANCY IN THIS PLAN AND ACTUAL FIELD CONDITIONS SHALL BE REPORTED TO THE DESIGN ENGINEER PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS AND DIMENSIONS SHOWN HEREON PRIOR TO BEGINNING CONSTRUCTION.
8. THE CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND RIGHT-OF-WAY, PUBLIC OR PRIVATE, PRIOR TO THE START OF CONSTRUCTION.
9. THE CONTRACTOR SHALL COORDINATE WITH ALL OWNERS TO DETERMINE THE LOCATION OF EXISTING LANDSCAPING, IRRIGATION LINES & PRIVATE UTILITY LINES. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO EXISTING LANDSCAPING, IRRIGATION LINES, AND PRIVATE UTILITY LINES.
10. THE CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE UPON COMPLETION OF THE PROJECT.
11. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND ADJOINING PROPERTY PROTECTED FROM DAMAGE.
12. THE CONTRACTOR SHALL KEEP THE AREA OUTSIDE THE "CONSTRUCTION LIMITS" BROOM CLEAN AT ALL TIMES.
13. THE CONTRACTOR SHALL CALL MISS DIG A MINIMUM OF 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
14. ALL PAVEMENT REPLACEMENT AND OTHER WORKS COVERED BY THESE PLANS SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWNSHIP, INCLUDING THE LATEST MICHIGAN DEPARTMENT OF TRANSPORTATION (MDOT) SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
15. THE CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE TO EXISTING UTILITIES.
16. NO ADDITIONAL COMPENSATION WILL BE PAID TO THE CONTRACTOR FOR ANY DELAY OR INCONVENIENCE DUE TO THE MATERIAL SHORTAGES OR RESPONSIBLE DELAYS DUE TO THE OPERATIONS OF SUCH OTHER PARTIES DOING WORK INDICATED OR SHOWN ON THE PLANS OR IN THE SPECIFICATION OR FOR ANY REASONABLE DELAYS IN CONSTRUCTION DUE TO THE ENCOUNTERING OR EXISTING UTILITIES THAT MAY OR MAY NOT BE SHOWN ON THE PLANS.
17. DURING THE CONSTRUCTION OPERATIONS, THE CONTRACTOR SHALL NOT PERFORM WORK BY PRIVATE AGREEMENT WITH PROPERTY OWNERS ADJACENT TO THE PROJECT.
18. IF WORK EXTENDS BEYOND NOVEMBER 15, NO COMPENSATION WILL BE DUE TO THE CONTRACTOR FOR ANY WINTER PROTECTION MEASURES THAT MAY BE REQUIRED BY THE ENGINEER.
19. NO TREES ARE TO BE REMOVED UNTIL MARKED IN THE FIELD BY THE ENGINEER.
20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE PROPERTY BEYOND THE CONSTRUCTION LIMITS INCLUDING BUT NOT LIMITED TO EXISTING FENCE, LAWN, TREES AND SHRUBBERY.
21. TRAFFIC SHALL BE MAINTAINED DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL SIGNS AND TRAFFIC CONTROL DEVICES. FLAG PERSONS SHALL BE PROVIDED BY THE CONTRACTOR IF DETERMINED NECESSARY BY THE ENGINEER. ALL SIGNS SHALL CONFORM TO THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AT NO COST TO THE TOWNSHIP. NO WORK SHALL BE DONE UNLESS THE APPROPRIATE TRAFFIC CONTROL DEVICES ARE IN PLACE.
22. ALL DEMOLISHED MATERIALS AND SOIL SPOILS SHALL BE REMOVED FROM THE SITE AT NO ADDITIONAL COST, AND DISPOSED OF IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
23. ANY EXISTING APPURTENANCES SUCH AS MANHOLES, GATE VALVES, ETC. SHALL BE ADJUSTED TO THE PROPOSED GRADE AND SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
24. ALL PERMANENT SIGNS AND PAVEMENT MARKINGS SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST REVISION OF THE MICHIGAN MUTCD MANUAL AND SHALL BE INCIDENTAL TO THE CONTRACT.
25. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL ITEMS REQUIRED FOR CONSTRUCTION OF THE PROJECT ARE INCLUDED IN THE CONTRACT, ANY ITEMS NOT SPECIFICALLY DESIGNATED IN THE PLANS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
26. THE CONTRACTOR IS RESPONSIBLE FOR HAVING A SET OF APPROVED CONSTRUCTION PLANS, WITH THE LATEST REVISION DATE, ON SITE PRIOR TO THE START OF CONSTRUCTION, IN THE EVENT OF ANY QUESTIONS PERTAINING TO THE INTENT OF THE CONSTRUCTION PLANS OR SPECIFICATIONS, THE CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER FOR A FINAL DETERMINATION FROM THE DESIGN ENGINEER.
27. THE CONTRACTOR, NOT THE OWNER OR THE ENGINEER, ARE RESPONSIBLE FOR THE MEANS, METHODS, AND SEQUENCE OF CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR SAFE EXECUTION OF THE PROJECT SCOPE IN ACCORDANCE WITH THE APPROVED CONSTRUCTION PLANS.
28. THE CONTRACTOR IS RESPONSIBLE FOR PRESERVING CONSTRUCTION STAKING AS NECESSARY. CONTRACTOR TO NOTIFY CONSTRUCTION SURVEYOR OF REPLACEMENT STAKES NEEDED WHICH SHALL BE AT THE CONTRACTORS EXPENSE.
29. THE OWNER AND/OR CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING FRANCHISE UTILITY SERVICES (CABLE, ELECTRIC, GAS, ETC.) OWNER AND/OR CONTRACTOR SHALL WORK WITH UTILITY COMPANIES ON FURNISHING SITE UTILITY LAYOUTS AND PROVIDING CONDUIT CROSSINGS AS REQUIRED.
30. DAMAGE TO ANY EXISTING UTILITIES OR INFRASTRUCTURE (INCLUDING PAVEMENT, CURB, SIDEWALK, ETC.) SHALL PROMPTLY BE REPLACED IN KIND AND SHALL BE AT THE CONTRACTORS EXPENSE.
31. COORDINATION OF TESTING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND PER ALL CITY/TOWNSHIP/COUNTY REQUIREMENTS. COPIES OF ALL TEST REPORTS SHALL BE FURNISHED TO THE DESIGN ENGINEER.
32. PRIOR TO THE START OF CONSTRUCTION, PROTECTION FENCING SHALL BE ERECTED AROUND THE TREE DRIPLINE OF ANY TREES INDICATED TO BE SAVED WITHIN THE LIMITS OF DISTURBANCE.
33. THE CONTRACTOR SHALL MAINTAIN DRAINAGE OF THE PROJECT AREA AND ADJACENT AREAS. WHERE EXISTING DRAINAGE FACILITIES ARE IMPACTED/DISTURBED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE ANY NECESSARY TEMPORARY DRAINAGE PROVISIONS.
34. SOIL BORING LOGS ARE REPRESENTATIVE OF SPECIFIC POINTS ON THE PROJECT SITE, AND IF PROVIDED TO THE CONTRACTOR ARE FOR INFORMATIONAL PURPOSES ONLY.
35. WHERE CITY/TOWNSHIP STANDARD CONSTRUCTION DETAILS/SPECIFICATIONS ARE PROVIDED AND ARE IN CONFLICT WITH NOTES AND SPECIFICATIONS HEREIN, THE CITY/TOWNSHIP STANDARD SHALL GOVERN.

INDEMNIFICATION STATEMENT

THE CONTRACTOR SHALL HOLD HARMLESS THE DESIGN PROFESSIONAL, MUNICIPALITY, COUNTY, STATE, AND ALL OF ITS SUB CONSULTANTS, PUBLIC AND PRIVATE UTILITY COMPANIES, AND LANDOWNERS FOR DAMAGES TO INDIVIDUALS AND PROPERTY, REAL OR OTHERWISE, DUE TO THE OPERATIONS OF THE CONTRACTOR AND/OR THEIR SUBCONTRACTORS.

CONTRACTOR TO FOLLOW MANUFACTURER SPECS/RECOMMENDATIONS THAT SUPERCEDE PLANS

GENERAL GRADING & SESC NOTES

- 1. THE CONTRACTOR SHALL HAVE IN PLACE ALL REQUIRED EROSION CONTROL METHODS AS INDICATED ON THE CONSTRUCTION PLANS AND AS REQUIRED BY GENERAL PRACTICE. SPECIFIC MEANS, METHODS AND SEQUENCES OF CONSTRUCTION MAY DICTATE ADDITIONAL SOIL EROSION CONTROL MEASURES BE NEEDED. THE CONTRACTOR SHALL COORDINATE WITH THE DESIGN ENGINEER ON THESE ANTICIPATED METHODS. ADDITIONAL SOIL EROSION CONTROL METHODS SHALL BE INCIDENTAL TO THE SCOPE OF WORK.
2. ACTUAL FIELD CONDITIONS MAY DICTATE ADDITIONAL OR ALTERNATE SOIL EROSION CONTROL MEASURES BE UTILIZED. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DEFICIENCIES OR FIELD CONDITIONS THAT WARRANT ADDITIONAL AND/OR ALTERNATIVE SESC MEASURES BE UTILIZED.
3. AT THE CLOSE OF EACH DAY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING ALL CONSTRUCTION OPERATIONS, MATERIALS, DEBRIS, ETC ARE CONTAINED ON-SITE.
4. AT THE CLOSE OF EACH WORKING DAY, ALL DRAINAGE STRUCTURES SHALL BE FREE OF DIRT AND DEBRIS AT THE FLOW LINE.
5. ALL SOIL EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE PER MDEGL REGULATIONS AND BEST PRACTICES. ALL SOIL EROSION CONTROL MEASURES SHALL BE MAINTAINED BY THE CONTRACTOR.
6. THE SOIL EROSION CONTROL MEASURES SHALL BE KEPT IN PLACE UNTIL SUCH A TIME THAT THE SITE IS DETERMINED TO BE ESTABLISHED WITH ACCEPTABLE AMOUNT OF VEGETATIVE GROUND COVER.
7. ALL AREAS DISTURBED BY THE CONTRACTOR BEYOND THE NORMAL CONSTRUCTION LIMITS OF THE PROJECT SHALL BE SODDED OR SEEDED AS SPECIFIED OR DIRECTED BY THE ENGINEER.
8. AFTER REMOVAL OF TOPSOIL, THE SUBGRADE SHALL BE COMPACTED TO 95% OF ITS UNIT WEIGHT.
9. ALL GRADING IN THE PLANS SHALL BE DONE AS PART OF THIS CONTRACT. ALL DELETERIOUS MATERIAL SHALL BE REMOVED FROM THE SUBGRADE PRIOR TO COMPACTING.
10. ALL ROOTS, STUMPS AND OTHER OBJECTIONABLE MATERIALS SHALL BE REMOVED AND THE HOLE BACKFILLED WITH SUITABLE MATERIAL. WHERE GRADE CORRECTION IS REQUIRED, THE SUBGRADE SHALL BE CUT TO CONFORM TO THE CROSS-SECTION AS SHOWN IN THE PLANS.
11. ALL EXCAVATION UNDER OR WITHIN 3 FEET OF PUBLIC PAVEMENT, EXISTING OR PROPOSED SHALL BE BACKFILLED AND COMPACTED WITH SAND (MDOT CLASS II).

GENERAL LANDSCAPE NOTES

- 1. ALL PLANT MATERIAL SHALL CONFORM TO THE REQUIREMENTS AND SPECIFICATIONS OF THE GOVERNING MUNICIPALITY. ALL STOCK SHALL BE NURSERY GROWN, CONFORMING TO ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK", AND IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICE. STOCK SHALL EXHIBIT NORMAL GROWTH HABIT AND BE FREE OF DISEASE, INSECTS, EGGS, LARVAE, & DEFECTS SUCH AS KNOTS, SUN-SCALD, INJURIES, ABRASIONS, OR DISFIGUREMENT. ALL PLANT MATERIAL SHALL BE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT.
2. ALL PLANT MATERIALS SHALL BE BALLED AND BURLAPPED OR CONTAINER STOCK. NO BARE ROOT STOCK IS PERMITTED. ALL PLANT BALLS SHALL BE FIRM, INTACT, AND SECURELY WRAPPED AND BOUND.
3. ALL PLANT BED MATERIALS SHALL BE EXCAVATED OF ALL BUILDING MATERIALS, OTHER EXTRANEANOUS OBJECTS, AND POOR SOILS TO A MINIMUM DEPTH OF 12-INCHES AND BACKFILLED TO GRADE WITH SPECIFIED PLANTING MIX (SEE BELOW).
4. PLANTING MIXTURE SHALL CONSIST OF 5 PARTS TOPSOIL FROM ON-SITE (AS SUPERP), 4 PARTS COARSE SAND, 1 PART SPHAGNUM PEAT MOSS (OR APPROVED COMPOST), AND 5 LBS OF SUPERPHOSPHATE FERTILIZER PER CU. YD. OF MIX. INGREDIENTS SHALL BE THOROUGHLY BLENDED FOR UNIFORM CONSISTENCY.
5. ALL PLANT BEDS AND INDIVIDUAL PLANTS, NOT OTHERWISE NOTED SHALL BE MULCHED WITH A 4-INCH LAYER OF SHREDED BARK MULCH. EDGE OF MULCH BEDS AS SHOWN. DECIDUOUS TREES IN LAWN AREAS SHALL RECEIVE A 5-FT DIAMETER CIRCLE OF MULCH AND CONIFER TREES 8-FT (PLANTED CROWN OF TREE) UNLESS OTHERWISE NOTED.
6. LANDSCAPE STONE SHALL BE INSTALLED WHERE NOTED OR INDICATED (HATCHED). STONE SHALL BE 3/4"-1-1/4" WASHED RIVER GRAVEL OR AS SELECTED AND SHALL BE INSTALLED TO A MINIMUM DEPTH OF 3-INCHES.
7. ALL LANDSCAPE BEDS, UNLESS OTHERWISE NOTED SHALL BE INSTALLED OVER WEED BARRIER FABRIC - WATER PERMEABLE FILTRATION FABRIC OF NON-WOVEN POLYPROPYLENE OR POLYESTER FABRIC. FABRIC SHALL BE OF SUITABLE THICKNESS FOR APPLICATION.
8. ALL PLANTS AND PLANT BEDS SHALL BE THOROUGHLY WATERED UPON COMPLETION OF PLANTING AND STAKING OPERATIONS.
9. THE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIALS FOR A PERIOD OF 1 YEAR FROM THE DATE THE WORK IS ACCEPTED, IN WRITING, BY THE LANDSCAPE ARCHITECT. THE CONTRACTOR SHALL REPLACE, WITHOUT COST TO THE OWNER, WITHIN A SPECIFIED PERIOD OF TIME, ALL DEAD PLANTS, AND ALL PLANTS NOT IN A VIGOROUS, THRIVING CONDITION, AS DETERMINED BY THE LANDSCAPE ARCHITECT, DURING AND AT THE END OF THE GUARANTEE PERIOD. REPLACEMENT STOCK SHALL CONFORM TO THE ORIGINAL SPECIFICATIONS.
10. EDGING SHALL BE PROVIDED FOR ALL LANDSCAPE BEDS NOT ADJACENT TO CONCRETE PAVEMENT. EDGING SHALL BE BLACK ALUMINUM EDGING, 3/16-INCH X 4-INCH. INSTALL PER MANUFACTURER'S INSTRUCTIONS, ALL EDGING SHALL BE INSTALLED IN STRAIGHT LINES OR SMOOTH CURVES WITHOUT IRREGULARITIES.
11. SOD SHALL BE DENSE, WELL ROOTED TURF, FREE OF WEEDS. IT SHALL BE COMPRISED OF A BLEND OF AT LEAST TWO KENTUCKY BLUE GRASSES AND ONE FESCUE. IT SHALL HAVE A UNIFORM THICKNESS OF 3/4-INCH AT TIME OF PLANTING, AND CUT IN UNIFORM STRIPS NOT LESS THAN 10-INCHES BY 18-INCHES. SOD SHALL BE KEPT MOIST AND LAID WITHIN 36-HOURS AFTER CUTTING.
12. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH A DENSE LAWN OF PERMANENT GRASSES, FREE OF LUMPS AND DEPRESSIONS. ALL SODDED AREAS THAT BROWN-OUT OR HAVE NOT FIRMLY KNITTED TO THE SOIL BASE WITHIN A PERIOD OF 1 MONTH SHALL BE REPLACED BY THE CONTRACTOR, AT NO COST TO THE OWNER.

SEED MIXTURE SHALL BE AS FOLLOWS:
KENTUCKY BLUEGRASS (CHOOSE 3 VARIETIES - ADLPHI, RUGBY, GLADE, OR PARADE) 30%
RUBY RED OR DAWSON RED FINE FESCUE 30%
ATLANTA RED FESCUE 20%
PENNFINE PERENNIAL RYE 20%
THE ABOVE SEED MIXTURE SHALL BE SOWN AT A RATE OF 250 LBS PER ACRE. PRIOR TO SEEDING, THE TOPSOIL SHALL BE FERTILIZED WITH A COMMERCIAL FERTILIZER WITH A 10-0-10 ANALYSIS:
10% NITROGEN - MIN 25% FROM A UREA FORMALDEHYDE SOURCE
0 % PHOSPHATE
10% POTASH - SOURCE POTASSIUM SULFATE OR POTASSIUM NITRATE

THE FIRST FERTILIZER APPLICATION SHALL BE AT A RATE OF 10 LBS PER 1000 SQ FT OF BULK FERTILIZER.
IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH A DENSE LAWN OF PERMANENT GRASSES, FREE OF LUMPS AND DEPRESSIONS. ANY PART OF THE AREA THAT FAILS TO SHOW A UNIFORM GERMINATION SHALL BE RE-SEEDED AND SUCH RE-SEEDED SHALL CONTINUE UNTIL A DENSE LAWN IS ESTABLISHED. DAMAGE TO SEEDED AREAS RESULTING FROM EROSION SHALL BE REPAIRED BY THE CONTRACTOR.

- 13. ALL AREAS OF THE SITE SCHEDULED FOR SEEDING OR SODDING SHALL FIRST RECEIVE A 6-INCH LAYER OF CLEAN, FRIABLE TOPSOIL. THE SOIL SHALL BE DISCED AND SHALL BE GRADED IN CONFORMANCE WITH THE GRADING PLAN.
14. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATION OF ALL UTILITIES AND TO INFORM THE LANDSCAPE ARCHITECT OF ANY CONFLICTS PRIOR TO COMMENCING LANDSCAPING.

GENERAL UTILITY NOTES

- 1. BEDDING SHALL EXTEND A MINIMUM OF 4" BELOW THE PIPE, UNLESS OTHERWISE NOTED ON THE PLANS. BEDDING SHALL BE OF UNIFORM GRADATION MDOT 6A+ STONE OR MDOT CLASS II GRANULAR MATERIAL FOR SANITARY AND STORM PIPE AND MDOT CLASS II GRANULAR MATERIAL ONLY FOR WATERMAIN.
2. WHERE UNSTABLE GROUND CONDITIONS ARE ENCOUNTERED, STONE BEDDING SHALL BE USED AS DIRECTED BY THE ENGINEER.
3. BACKFILL SHALL BE OF A SUITABLE MATERIAL AND SHALL BE FREE OF ANY ORGANIC MATERIALS AND ROCKS.
4. BACKFILL ABOVE THE PIPE SHALL BE OF GRANULAR MATERIAL MDOT CLASS II TO A POINT 12" ABOVE THE TOP OF THE PIPE. THE TRENCH IS NOT WITHIN THE INFLUENCE OF THE ROAD. THE TRENCH SHALL BE COMPACTED AND UTILIZED FROM A POINT 12" ABOVE THE PIPE TO GRADE. WHERE THE TRENCH IS WITHIN A 1:1 INFLUENCE OF THE ROAD, GRANULAR MATERIAL, MDOT CLASS II OR III, IS TO BE PLACED AND COMPACTED IN LAYERS NOT EXCEEDING 12" IN THICKNESS. COMPACTION SHALL BE 95% AS DETERMINED BY AASHTO T99.
5. 18" MINIMUM VERTICAL SEPARATION AND 10" HORIZONTAL SEPARATION IS TO BE MAINTAINED BETWEEN WATERMAIN AND SANITARY/STORM SEWER TO THE MAXIMUM EXTENT POSSIBLE.

GENERAL STORM NOTES

- 1. ALL STORM PIPE LENGTHS ARE SHOWN FROM C/L TO C/L OF STRUCTURE OR FROM C/L OF STRUCTURE TO DISCHARGE END OF FLARED END SECTION.
2. STORM PIPE MATERIALS SHALL BE AS FOLLOWS:
2.1. RCP(REINFORCED CONCRETE PIPE); SHALL MEET THE REQUIREMENTS OF ASTM C76 WITH MODIFIED GROOVED TONGUE AND RUBBER GASKETS MEETING THE REQUIREMENTS OF ASTM C443. RCP TO BE EITHER CLASS IV OR V AS CALLED OUT ON THE PLANS.
3. STORM PIPE JOINTS SHALL MEET THE REQUIREMENTS OF ASTM D3212. HDPE AND PP PIPE GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477.
4. ALL STORM PIPE TO HAVE WATERTIGHT PREMIUM JOINTS, UNLESS OTHERWISE NOTED ON THE PLANS.
5. STORM DRAINAGE STRUCTURES SHALL BE FURNISHED WITH STEPS WHICH SHALL BE STEEL ENCASED WITH POLYPROPYLENE PLASTIC OR EQUIVALENT. STEPS SHALL BE SET AT 16" CENTER TO CENTER.
6. FLARED END SECTIONS DISCHARGING STORM WATER SHALL RECEIVE A MINIMUM OF 10 SQ YDS OF PLAIN COBBLESTONE RIP RAP WITH A MINIMUM STONE SIZE OF 6" AND SHALL BE PLACED ON A GEOTEXTILE FABRIC WRAP.
7. ALL CATCH BASINS WITHIN THE ROADWAY SHALL INCLUDE INSTALLATION OF 6" DIAMETER PERFORATED PIPE SUBDRAIN.
8. STORM DRAINAGE STRUCTURE COVERS SHALL BE OF THE FOLLOWING (OR APPROVED EQUAL):
COVER USE FRAME GRATE/BACK
'A' MANHOLE 1040 TYPE 'B'
'D' PARKING LOTS 1040/5100 TYPE 'M1' GRATE OR 5105 TYPE 'M1' GRATE
'E' LAWN 1040 TYPE 'O2' GRATE


GENERAL SANITARY NOTES

- 1. ALL SANITARY PIPE LENGTHS ARE SHOWN FROM C/L OF STRUCTURE TO C/L OF STRUCTURE.
2. SANITARY PIPE MATERIALS SHALL BE AS FOLLOWS:
2.1. HDPE DR-11 (SANITARY FORCEMAIN)
3. ALL PVC SDR SANITARY SEWER PIPE SHALL MEET THE REQUIREMENTS OF ASTM D3034 AND D2241. PVC SCHD 40 PIPE SHALL MEET THE REQUIREMENTS OF ASTM D1785. GASKET JOINTS FOR SANITARY PIPE SHALL MEET THE REQUIREMENTS OF ASTM D3139 AND D3212.
4. SANITARY STRUCTURES SHALL BE FURNISHED WITH STEPS WHICH SHALL BE STEEL ENCASED WITH POLYPROPYLENE PLASTIC OR EQUIVALENT. STEPS SHALL BE SET AT 16" CENTER TO CENTER.
5. ALL NEW MANHOLES SHALL BE MINIMUM 4' DIAMETER, PRECAST MANHOLE SECTIONS AND AN ECCENTRIC CONE. PRECAST MANHOLE JOINTS SHALL BE INSTALLED WITH BUTYL ROPE MEETING THE REQUIREMENTS OF ASTM C990.
6. MANHOLES SHALL BE CONSTRUCTED WITH FLOW CHANNEL WALLS THAT ARE FORMER, AT A MINIMUM, TO THE SPRINGLINE OF THE PIPE.
7. ALL NEW MANHOLES SHALL HAVE AN APPROVED FLEXIBLE, WATERTIGHT SEALS WHERE PIPES PASS THROUGH MANHOLE WALLS.
8. ALL MANHOLES SHALL BE PROVIDED WITH WATERTIGHT COVERS. COVERS TO BE EJCO 1040 TYPE 'A' SOLID COVER.
9. A MAXIMUM OF 12" OF GRADE ADJUSTMENT RINGS SHALL BE USED TO ADJUST THE FRAME ELEVATION. BUTYL ROPE SHALL BE USED BETWEEN EACH ADJUSTMENT RING.
10. SANITARY SEWER LATERALS SHALL HAVE A MINIMUM SLOPE OF 1.0%.
11. CLEANOUTS SHALL BE INSTALLED EVERY 100', AT ALL BENDS AND STUBS.


GENERAL WATERMAIN NOTES

- 1. WATERMAIN PIPE MATERIALS SHALL BE AS FOLLOWS:
1.1. D.I.P. CL-52 (WATERMAIN)
1.2. HDPE DR-9 (WATER LATERAL - CURB STOP TO STUB)
2. WATERMAIN FITTINGS SHALL BE OF DUCTILE IRON WITH CEMENT MORTAR LINING AND MECHANICAL JOINTS CONFORMING TO AWWA C110.
3. WATERMAINS SHALL BE DISINFECTED IN ACCORDANCE WITH AWWA C651. BAC-T SAMPLES SHALL BE TAKEN IN ACCORDANCE WITH R235.11110 OF THE ADMINISTRATIVE RULES PROMULGATED UNDER MICHIGAN SAFE DRINKING WATER ACT, 1976 PA 399, AS AMENDED.
4. ALLOWABLE LEAKAGE OR HYDROSTATIC PRESSURE TESTING SHALL BE IN ACCORDANCE WITH AWWA C600 AND C605.
5. MAXIMUM DEFLECTION AT PIPE JOINTS SHALL BE IN ACCORDANCE WITH PIPE MANUFACTURERS CURRENT RECOMMENDATIONS AND AWWA SPECIFICATIONS.
6. A FULL STICK OF PIPE SHALL BE LAID CENTERED AT A PIPE CROSSING IN ORDER TO MAINTAIN THE MAXIMUM SEPARATION OF WATERMAIN JOINT TO THE CROSSING PIPE.
7. WATERMAIN SHALL BE INSTALLED WITH A MINIMUM OF 5.5' OF COVER FROM FINISHED GRADE TO TOP OF PIPE AND NO MORE THAN 8' OF COVER, UNLESS SPECIAL CONDITIONS WARRANT.
8. WATERMAIN VALVES SHALL BE IRON BODY RESILIENT WEDGE GATE VALVES, NON-RISING STEMS, COUNTERCLOCKWISE OPEN, AWWA C509.
9. THE BREAKAWAY FLANGE AND ALL BELOW GRADE FITTINGS SHALL HAVE STAINLESS STEEL NUTS AND BOLTS.


LINES & HATCHES LEGEND




LIGHTING LEGEND



LANDSCAPE LEGEND



SYMBOL LEGEND



ABBREVIATIONS



- FFE FINISHED FLOOR ELEVATION
BFE BASEMENT FLOOR ELEVATION
GFE GARAGE FLOOR ELEVATION
FG FINISHED GRADE
T/A TOP OF ASPHALT
T/C TOP OF CONCRETE/CURB
T/W TOP OF WALK
T/P TOP OF PIPE
B/P BOTTOM OF PIPE
F/L FLOW LINE
RIM RIM ELEVATION (AT FLOW LINE)
INV INVERT ELEVATION
MH MANHOLE
CB CATCH BASIN
RY REAR YARD
YD YARD DRAIN
RD ROOF DRAIN
FES FLARED END SECTION
CMP CORRUGATED METAL PIPE
GPP CORRUGATED PLASTIC PIPE
RCP REINFORCED CONCRETE PIPE
HDPE HIGH DENSITY POLYETHYLENE
PVC POLYVINYL CHLORIDE
DIP DUCTILE IRON PIPE
GV GATE VALVE
GVW GATE VALVE IN WELL
GVB GATE VALVE IN BOX
HYD HYDRANT
FDC FIRE DEPARTMENT CONNECTION
UP UTILITY POLE
NFV NOT FIELD VERIFIED TO BE REMOVED
L LIBER
P PAGE
L.C.R. LIVINGSTON COUNTY RECORDS
(M&R) MEASURED AND RECORD
L.O.B. POINT OF BEGINNING

THE LOCATION AND ELEVATION OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THESE DRAWINGS ARE ONLY APPROXIMATE. NO GUARANTEE IS MADE FOR THE ACCURACY OF THESE UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND DEPTH OF ALL UTILITIES CROSSING IN THE FIELD PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE PLANS.

BEBOSS Engineering
Engineers Surveyors Planners Landscape Architects
3121 E. GRAND RIVER AVE.
HOWELL, MI. 48843
517.546.4836 FAX 517.548.1670

SCHOOL BELL CHILDCARE
PROJECT: SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
4501 WEST HIGHLAND ROAD
MIFORD, MI 48380
248.830.9542
PREPARED FOR:
TITLE:
DATE:
REVISION PER:
DESIGNED BY: BL
DRAWN BY: JP
CHECKED BY:
SCALE: NO SCALE
JOB NO: 24-048
DATE: 05/31/24
SHEET NO. 2

SEE SHEET 2 FOR GENERAL NOTES AND LEGEND



SITE DATA:

HIGHLAND TOWNSHIP
PARCEL #11-30-101-002
4501 WEST HIGHLAND ROAD, MILFORD, MI 48380
1.62 AC ±

ZONING: LAKE & VILLAGE (LV)
SCHOOL DISTRICT: HURON VALLEY SCHOOLS

EXISTING SITE USE: SCHOOL BELL CHILDCARE
EXISTING CHILDCARE BLDG SF: 3,600 GSF ±
EXISTING PLAYGROUND SF: 10,313 GSF ±

MAX. LOT COVERAGE: 35.0% BLDG,
BUILDABLE AREA: 0.79 AC ± (34,363 SQ FT)
EXISTING LOT COVERAGE: 5.09% BLDG, 14.6% IMPERVIOUS
PROPOSED LOT COVERAGE: 15.4% BLDG, 34.7% IMPERVIOUS

MIN. LOT AREA REQUIRED FOR ZONING: 1.00 ACRE
EX. LOT AREA: 1.62 AC ± (70,754 SQ FT) + 0.03 AC ± (1,744 SF) DRIVEWAY APPROACH & CURB
MIN. LOT WIDTH: 120 FT TOTAL EXISTING LOT WIDTH: 156.08 FT

IMPERVIOUS AREAS =

PROPOSED ASPHALT PARKING	10,248 SF (0.24 AC)
PROPOSED ASPHALT DRIVEWAY APPROACH - OFFSITE	7,359 SF (0.03 AC)
PROPOSED CONCRETE WALK	1,764 SF (0.04 AC)
PROPOSED CONCRETE CURB - OFFSITE	385 SF (0.01 AC)
PROPOSED DUMPSTER PAD	240 SF (0.01 AC)
EXISTING BUILDING	3,600 SF (0.08 AC)
PROPOSED BUILDING	7,621 SF (0.17 AC)
SUBTOTAL:	25,217 SF (0.58 AC)

PERVIOUS AREAS =

MODIFIED PLAYGROUND	13,196 SF (0.30 AC)
EXISTING LAWN/VEGETATION	34,085 SF (0.78 AC)
SUBTOTAL:	47,281 SF (1.08 AC)


TOTAL SITE AREAS = TOTAL: 70,754 SF (1.62 AC) + 1,359 SF (0.03 AC) + 385 SF (0.01 AC)

MIN. BLDG. SETBACKS REQUIRED: EXISTING BLDG SETBACKS: PROPOSED BLDG SETBACKS:

RIGHT-OF-WAY:	33-FT	33-FT	33-FT
FRONT:	40-FT	20-FT	40-FT
SIDE:	30-FT: 10-FT MIN SIDE	47-FT	10-FT
REAR:	40-FT	103-FT	52-FT
MAX BLDG HGT:	28-FT	25-FT (2-STORY)	27-FT (1-STORY)

PARKING CALCULATION:
THE EXISTING BUILDING WILL CONTINUE TO BE USED FOR DAY CARE PURPOSES. PRIMARY CARE, INCLUDING STAFFING AND CHILDCARE, WILL INSTEAD OCCUR IN THE PROPOSED BUILDING. THE NEW BUILDING WILL HAVE 13 EMPLOYEES AND BE LICENSED FOR 96 CHILDREN. THE NUMBER OF REQUIRED SPACES ON SITE IS EQUAL TO 2 SPACES + 1 SPACE/8 CHILDREN WHICH TOTALS 14 REQUIRED SPACES, INCLUDING 1 VEHICLE ACCESSIBLE SPACE.

TOTAL PROVIDED PARKING: 15 SPACES (INCLUDING 1 VEHICLE ACCESSIBLE SPACE)



VEHICLE TRIP GENERATION TABLE

LAND USE DESCRIPTION*	ITE CAT.	SIZE	UNIT	WEEKDAY AM PEAK (7-9AM)			WEEKDAY PM PEAK (4-6PM)			REMARKS
				TRIPS	IN	OUT	TRIPS	IN	OUT	
PROPOSED BUILDING										
DAY CARE CENTER	565	96	STUDENTS	75	40	35	-	76	36	40
ENTERING (%) / EXITING (%)				100%	53%	47%	-	100%	47%	53%

* TRIP DATA PER INSTITUTE OF TRAFFIC ENGINEERS (ITE) TRIP GENERATION MANUAL 10TH EDITION - VOLUME 2

GENERAL NOTES:
SUBSURFACE UTILITIES NOT LOCATED FOR THIS SURVEY MAY EXIST. IT IS THE RESPONSIBILITY OF THE OWNER OF THE RESPECTIVE UTILITY TO ACCURATELY LOCATE SUCH UTILITIES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE MUNICIPALITY, THE COUNTY, AND THE STATE OF MICHIGAN.

ALLOW THREE WORKING DAYS BEFORE YOU DIG, CALL MISS DIG TOLL FREE 1-800-482-7171

FOR SITE PLAN APPROVAL ONLY!
NOT FOR CONSTRUCTION




BEBOSS
Engineering
Engineers Surveyors Planners Landscape Architects
3121 E. GRAND RIVER AVE.
HOWELL, MI. 48843
517.546.4836 FAX 517.548.1670

SCHOOL BELL CHILDCARE
SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
4501 WEST HIGHLAND ROAD
MILFORD, MI 48380
248.830.9542



SITE PLAN

PROJECT	
PREPARED FOR	
TITLE	
DATE	
DESIGNED BY:	BL
DRAWN BY:	JP
CHECKED BY:	
SCALE:	1"=20'
JOB NO:	24-048
DATE:	05/31/24
SHEET NO.	5

SEE SHEET 2 FOR GENERAL NOTES AND LEGEND



DEVELOPMENT: TWENTY-TWO (22) TREES ARE TO BE REMOVED FOR THE DEVELOPMENT OF THE SITE - ALL IN THE EAST, UNDEVELOPED AREA. NO TREES ARE TO BE RELOCATED. REMOVED TREES ARE WITHIN THE PROPOSED BUILDING OUTLINE AND WHERE IMPACTED BY THE EXPANDED PARKING LOT. MATURE TREES AROUND THE PERIMETER OF THE SITE WILL BE PRESERVED DURING CONSTRUCTION. PORTIONS OF THE EXISTING LOT AREA WILL BE UTILIZED FOR TOPSOIL STOCKPILING AND MATERIAL STAGING AREAS (AS NOTED ON THE PLAN).



SOIL EROSION CONTROL MEASURES

1T	1	STRIPPING & STOCKPILING TOPSOIL	TOPSOIL MAY BE STOCKPILED ABOVE BARRON AREAS TO ACT AS A DIVERSION STOCKPILE SHOULD BE TEMPORARILY SEED
2P	2	SELECTIVE GRADING & STRIPPING	WATER CAN BE DEFLECTED TO MINIMIZE EROSION FLATTER SLOPES EASE EROSION PROBLEMS
6P	6	SEEDING WITH MULCH AND/OR MATING	FACILITATES ESTABLISHMENT OF VEGETATIVE COVER (EFFECTIVE FOR SLOPES WITH LOW VELOCITY EASILY PLACED IN SMALL QUANTITIES BY INEXPERIENCED PERSONNEL SHOULD INCLUDE PERMANENT TOPSOIL BED)
14T	14	AGGREGATE COVER	STABILIZES SOIL SURFACE, THIS MINIMIZES EROSION FORMS PROTECTION THAT IN ADVANCE HIGHER MAY BE USED AS PART OF PERMANENT BASE CONSTRUCTION OF PAVED AREAS
15P	15	FRAMING	PROTECTS AREAS WHICH CANNOT OTHERWISE BE PROTECTED, BUT INCREASES RUNOFF VELOCITY IRREGULAR SURFACE WILL HELP SLOW VELOCITY
35P	35	STRIP SWEEP	SYSTEM REMOVES COLLECTED RUNOFF FROM SITE, PARTICULARLY FROM PAVED AREAS CAN ACCEPT LARGE CONCENTRATIONS OF RUNOFF CONDUCTS RUNOFF TO MUNICIPAL SEWER SYSTEM OR STABILIZED OUTFALL LOCATION USE CHECK BASINS TO COLLECT SEDIMENT
36P	36	CATCH BASIN, SWEEP NET	COLLECTS HIGH VELOCITY CONCENTRATED RUNOFF MAY USE FILTER CLOTH OVER INLET
40T	40	INLET SEDIMENT FILTER	EASY TO SHAKE COLLECTS SEDIMENT MAY BE CLEANED AND EXPANDED AS NEEDED
54T	54	SILT FENCE	USES GEOTEXTILE FABRIC AND POST OR POLES. EASY TO CONSTRUCT AND LOCATE AS NECESSARY. (SEE DETAIL SHEET)

T= TEMPORARY, P= PERMANENT
TOTAL DISTURBED AREA= 1.18 AC.

SURFACE WATER & COUNTY DRAINS
WETLAND - APPROXIMATELY 800 FT WEST TO S TIPISICO LAKE RD
LAKES - APPROXIMATELY 4,250 FT NORTH TO DUNHAM LAKE
BASEINS - APPROXIMATELY 1,110 FT SOUTH AT S TIPISICO LAKE RD
PONDS - APPROXIMATELY 855 FT SOUTHEAST AT POMMORE DR

PROPOSED CONST. SCHEDULE FOR THE YEAR 2024

ACTIVITY	MAY	JUNE	JULY	AUG	SEPT	OCT
DEMO & CLEAR						
MASS GRADING						
UNDERGROUND UTILITY						
FINAL GRADING						
SEED & MULCH						

CONTROLS & MEASURES NARRATIVE

ACTIVITY	DESCRIPTION
MAINTAIN LANDSCAPING, REPLACE MULCH	COLLECT GRASS, TREE, AND SHRUB CLIPPINGS. DISPOSE IN APPROVED CONTAINER. REPLACE DEAD SOD, TREES AND SHRUBS.
CLEAN INLETS	REMOVE LITTER, SEDIMENT, AND DEBRIS. DISPOSE OF IN APPROVED LANDFILL.
COLLECT LITTER	DISPOSE OF WITH INLET DEBRIS.
SWEEP PARKING LOT	REMOVE MUD, DIRT, GREASE, AND OIL WITH PERIODIC SWEEPING
DUST CONTROL	SPRINKLE WATER AS NEEDED

CONTROLS & MEASURES POST CONSTRUCTION SEQUENCE

ACTIVITY	WEEKLY	MONTHLY	AS REQUIRED
MAINTAIN LANDSCAPING, REPLACE MULCH	X	X	X
CLEAN INLETS		X	X
COLLECT LITTER	X		X
SWEEP PARKING LOT		X	X

CONSTRUCTION SEQUENCE

THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT EROSION IS MINIMIZED AND THAT COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, REGULATIONS, AND ORDINANCES IS MAINTAINED THROUGHOUT EXECUTION OF THIS PROJECT.

1 DAYS	1. INSTALL SILT FENCE AS SHOWN ON PLANS.
5 DAYS	2. ROUGH GRADE AND INSTALL STORM DRAINAGE.
1 DAY	3. INSTALL INLET PROTECTION ON STORM INLETS.
180 DAY	4. START BLDG. CONSTRUCTION
4 DAYS	5. INSTALL PAVEMENT
4 DAYS	6. FINE GRADE AROUND BUILDING, SPREAD TOPSOIL, SEED OR SOD AS APPLICABLE.
1 DAY	7. REMOVE ALL EROSION CONTROL STRUCTURES.
1 DAY	8. REMOVE ACCUMULATED SILT FROM ALL EXISTING DRAINAGE.

BEBOSS Engineering
 Engineers Surveyors Planners Landscape Architects
 3121 E. GRAND RIVER AVE.
 HOWELL, MI. 48843
 517.546.4836 FAX 517.548.1670

SCHOOL BELL CHILDCARE
 SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
 4501 WEST HIGHLAND ROAD
 MILFORD, MI 48380
 248.830.9542

PROJECT	PREPARED FOR	TITLE	DATE
SCHOOL BELL CHILDCARE	SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE	SOIL EROSION SEDIMENTATION CONTROL PLAN	

DESIGNED BY:	BL
DRAWN BY:	JP
CHECKED BY:	
SCALE:	1"=20'
JOB NO:	24-048
DATE:	05/31/24
SHEET NO.	7

DYODS™
Design Your Own Detention System

CONTECH
CMP DETENTION SYSTEMS

For design assistance, drawings, and pricing send completed worksheet to: dyods@contech-cpi.com

Project Summary

Date: 4/18/2024
 Project Name: School Bell Childcare
 City / County: Highland/Oakland
 State: MI
 Designed By: JMP
 Company: Boss Engineering
 Telephone: 517.546.4836

Enter information in Blue Cells

Corrugated Metal Pipe Calculator

Storage Volume Required (cf):	5,000	
Limiting Width (ft):	26.00	
Invert Depth Below Asphalt (ft):	6.00	
Solid or Perforated Pipe:	Perforated	15.90 ft² Pipe Area
Shape Or Diameter (in):	54	
Number Of Headers:	1	
Spacing between Barrels (ft):	2.25	
Stone Width Around Perimeter of System (ft):	0	
Depth A: Porous Stone Above Pipe (in):	0	
Depth C: Porous Stone Below Pipe (in):	0	
Stone Porosity (0 to 40%):	0	

System Sizing

Pipe Storage:	5,038 cf	
Porous Stone Storage:	0 cf	
Total Storage Provided:	5,038 cf	100.8% Of Required Storage
Number of Barrels:	4 barrels	
Length per Barrel:	73.0 ft	
Length Per Header:	24.8 ft	
Rectangular Footprint (W x L):	24.75 ft x 77.5 ft	



CONTECH Materials

Total CMP Footage:	317 ft
Approximate Total Pieces:	18 pcs
Approximate Coupling Bands:	17 bands
Approximate Truckloads:	5 trucks

Construction Quantities**

Total Excavation:	427 cy
Porous Stone Backfill For Storage:	133 cy stone
Backfill to Grade Excluding Stone:	107 cy fill

**Construction quantities are approximate and should be verified upon final design.




System Layout

Barrel 12	0
Barrel 11	0
Barrel 10	0
Barrel 9	0
Barrel 8	0
Barrel 7	0
Barrel 6	0
Barrel 5	0
Barrel 4	73
Barrel 3	73
Barrel 2	73
Barrel 1	73


Barrel Footage (w/o headers)

SEE SHEET 2 FOR GENERAL NOTES AND LEGEND



STRUCTURE FRAMES & COVERS

COVER	TYPE	USE	EAST JORDAN (OR EQUAL)	TYPE OF COVER OR GRATE
A	MH	ALL	1040	TYPE "B"
D	CB & INLET	PARKING LOTS	1040 5100	TYPE "M1" GRATE 5105 TYPE "M1" GRATE
E	CB & INLET	LAWN AREA OR DITCH	1040	TYPE "O2"




THE LOCATION AND ELEVATION OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THESE DRAWINGS ARE ONLY APPROXIMATE. NO CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.

BEBOSS
Engineering
Engineers Surveyors Planners Landscape Architects
3121 E. GRAND RIVER AVE.
HOWELL, MI. 48843
517.546.4836 FAX 517.548.1670

PROJECT	SCHOOL BELL CHILDCARE
PREPARED FOR	SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
TITLE	UTILITY PLAN
DESIGNED BY:	BL
DRAWN BY:	JP
CHECKED BY:	
SCALE:	1"=20'
JOB NO:	24-048
DATE:	05/31/24
SHEET NO.	8

SEE SHEET 2 FOR GENERAL NOTES AND LEGEND




PRUNE BROKEN OR MISSHAPEN - RETAIN NATURAL SHAPE

IN SODDED AREAS PLACE SOD TO BOTTOM OF EARTH SAUCER


REMOVE BALLING MATERIAL &/OR CONTAINER. FINISH GRADE MIN. 4" SHREDDED MULCH

6" MIN. PLANTING MIXTURE BETWEEN BALL & PIT WALL UNDISTURBED SUBGRADE SCARIFY TO 2" DEPTH

SHRUB PLANTING DETAIL
(NO SCALE)




PLANT LIST					
KEY	QUAN.	BOTANICAL NAME	COMMON NAME	SIZE	REMARK
DECIDUOUS TREES					
AG	3	Amelanchier x Grandiflora 'Autumn Brilliance'	Autumn Brilliance Serviceberry	6' hgt.	B-B
CC	6	Cercis canadensis 'The Rising Sun' (JNU)	Rising Sun Redbud	2" cal.	B-B
NS	1	Nyssa sylvatica 'Northern Splendor'	Northern Splendor Black Gum	2.5" cal.	B-B
QM	2	Quercus macrocarpa 'JFS-KWS'	Urban Pinnacle Oak	2.5" cal.	B-B
QB	6	Quercus bicolor 'Bonnie and Mike'	Beacon Oak (Columnar)	2.5" cal.	B-B
CONIFER TREES					
PG	13	Picea glauca	White Spruce	6' hgt.	B-B
DECIDUOUS SHRUBS					
RA	17	Rhus aromatica 'Lacette'	Lacette Fragrant Sumac	24"/#3	Cont.
DP	10	Symphoricarpos sp.	Proud Berry Coralberry	18"/#3	Cont.
TC	3	Taxus canadensis	Canada Yew	36"/#5	Cont.
VD	9	Viburnum dentatum 'Christom'	Blue Muffin Arrowwood Viburnum	36"/#5	Cont.



DECIDUOUS TREE PLANTING DETAIL
(NO SCALE)

- NEVER CUT THE LEADER
- RUBBER HOSE POSITIONED DIRECTLY ABOVE THE TREE BRANCH
- DOUBLE STRAND = 12 GAUGE TWISTED WIRE
- TREE STAKES, THREE 120" APART
- PULL WIRE THROUGH HOLE AND AROUND STAKE BEFORE TYING
- BEFORE BACK FILLING AROUND PLANT, REMOVE ALL PLASTIC BALLING MATERIAL & METAL CONTAINERS. PUNCH HOLES IN FIBER POTS TO PROVIDE DRAINAGE.



LANDSCAPE CALCULATIONS

PROJECT INFORMATION:	1.62 AC TOTAL SITE
SITE SIZE / AREA OF WORK:	LV (LAKES AND VILLAGES)
ADJACENT ZONING / USES:	EAST - LV / SINGLE-FAMILY RESIDENTIAL WEST - LV (LAKES AND VILLAGES) NORTH - M-59 RIGHT-OF-WAY SOUTH - LV / SINGLE-FAMILY RESIDENTIAL
PARKING LOT:	14 NEW SPACES + 1 ADA SPACE PROVIDED IN 1 PARKING LOT (15 TOTAL SPACES)
REQUIRED:	
GENERAL:	SECTION 12.03 (B) (4) THE PRESERVATION AND INCORPORATION OF EXISTING TREES IS ENCOURAGED
SCREENING BETWEEN LAND USES:	SECTION 12.04 SCREENING BETWEEN LAND USES MIN 6FT HEIGHT VISUAL SCREEN REQUIRED FOR "INTENSE USE" PLAN COMMISSION SHALL DETERMINE TYPE CONIFER HEDGE, SOLID WALL, OR DECORATIVE FENCE
PARKING LOT LANDSCAPING:	SECTION 12.05 (A) 1 TREE + 3 SHRUBS / 8 SPACES. SEPARATE LANDSCAPE ISLANDS MIN. 200 SQFT EACH THE PLANNING COMMISSION MAY APPROVE AN EQUIVALENT AMOUNT OF LANDSCAPE PLANTINGS AT THE PERIMETER OF PARKING LOTS WHERE LANDSCAPING WITHIN PARKING LOTS WOULD BE IMPRACTICAL DUE TO THE SIZE OF THE PARKING LOT, DETRIMENTAL TO SAFE AND EFFICIENT TRAFFIC FLOW, OR WOULD CREATE AN UNREASONABLE BURDEN FOR MAINTENANCE AND SNOW PLOWING.
REQUIRED LANDSCAPING ADJACENT TO ROAD PUBLIC RIGHTS-OF-WAY:	SECTION 12.05 (B) PARKING LOTS SHALL BE SCREENED FROM VIEW THAT ARE VISIBLE FROM ALL RIGHTS-OF-WAY BY A LANDSCAPED BERM, WALL, OR SUFFICIENT PLANTINGS 3 FEET IN HEIGHT.
GREENBELTS:	SECTION 12.06 MINIMUM 20 FEET IN WIDTH FOR ALL NON-RESIDENTIAL PROPERTIES FRONTING HIGHLAND ROAD (M-59) AND 12 FEET IN WIDTH FOR ALL OTHER NON-RESIDENTIAL USES. MIN 1 TREE/ 30 LI.FT FRONTAGE ROW (NOT INCL. DRIVES)
SITE LANDSCAPING:	THE GREENBELT SHALL BE LANDSCAPED WITH A MINIMUM OF 1 DECIDUOUS TREE FOR EVERY 30 LINEAL FEET, OR FRACTION THEREOF OF FRONTAGE ABUTTING A PUBLIC ROAD RIGHT-OF-WAY. THE REMAINDER OF THE GREENBELT SHALL BE LANDSCAPED WITH TREES, GRASSES, GROUND COVERS, AND SHRUBS.
SCREENING OF TRASH CONTAINERS:	SECTION 12.09 SCREENED ON ALL SIDES WITH OPAQUE FENCE OR WALL AND GATE AT LEAST 6FT HIGH.
PROVIDED:	
SCREENING BETWEEN LAND USES:	PROPOSE: 6 NEW CONIFER TREES, 1 NEW DECIDUOUS TREE, 5 EXISTING DECIDUOUS TREES SCREEN SOUTH. 3 EXISTING DECIDUOUS TREES SCREEN EAST.
PARKING LOT LANDSCAPING:	(15 SPACES TOTAL) X (1 TREE/8 SPACES) = 1.75 TREES = 2 TREES (15 SPACES TOTAL) X (3 SHRUBS/8 SPACES) = 5.25 SHRUBS = 6 SHRUBS PROPOSE LANDSCAPING AT THE PERIMETER OF THE LOT DUE TO SMALL SIZE OF LOT FOR SAFE AND EFFICIENT TRAFFIC FLOW.
LANDSCAPING ADJACENT TO PUBLIC RIGHTS-OF-WAY:	4-FOOT HIGH-OPACITY DECIDUOUS SHRUB ROW ALONG M59 SIDE OF LOT (17) SHRUBS
GREENBELTS:	HIGHLAND ROAD/M59: 20 FEET 425/30 LINEAL FEET = 15 DECIDUOUS TREES 1 EXISTING DECIDUOUS TREE + 14 DECIDUOUS TREES
SITE LANDSCAPING:	POHMORE DRIVE: 20 FEET 35.50+76.50+60.00= 172 LINEAL FEET, 172/30 LINEAL FEET = 6 DECIDUOUS TREES 5 EXISTING DECIDUOUS TREES + 1 DECIDUOUS TREE
SCREENING OF TRASH CONTAINERS:	PROVIDED BY 6' HEIGHT WALLED ENCLOSURE WITH GATE INCLUDED
REQUIRED:	7,507 SQFT X (15) = 10585 SQ.FT. OR 0.243 ACRE
PROVIDED:	WEST SIDE YARD: 7053 SQFT EAST SIDE YARD: 2943 SQFT FOUNDATION PLANTING: 914 SQFT REAR YARD: 5205 SQFT
TOTAL LANDSCAPED:	16115 SQFT OR 0.370 ACRE
CONSISTING OF PRESERVED TREES AND LAWN AREAS AND FOUNDATION PLANTINGS (AC COUNT)	

BEBOSS
Engineering
Engineers Surveyors Planners Landscape Architects
3121 E. GRAND RIVER AVE.
HOWELL, MI. 48843
517.546.4836 FAX 517.548.1670

SCHOOL BELL CHILDCARE
SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
4501 WEST HIGHLAND ROAD
MIFORD, MI 48860
248.830.9542

PROJECT	PREPARED FOR	TITLE	DATE
SCHOOL BELL CHILDCARE	SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE	LANDSCAPE PLAN	
DESIGNED BY:	TC		
DRAWN BY:	TC		
CHECKED BY:	PC		
SCALE:	1" = 20'		
JOB NO:	24-048		
DATE:	05/31/24		
SHEET NO.	10		



SEE SHEET 2 FOR GENERAL NOTES AND LEGEND


PROJECT SUMMARY

CALCULATION DETAILS
LOADING = H20/S16S
APPROX. LINEAR FOOTAGE = 315 LF

STORAGE SUMMARY
STORAGE VOLUME REQUIRED = 5,000 CF
PIPE STORAGE VOLUME = 5,006 CF
BACKFILL STORAGE VOLUME = 0 CF
TOTAL STORAGE PROVIDED = 5,006 CF

PIPE DETAILS
DIAMETER = 54"
CORRUPTION = 5x1
GAGE = 16
COATING = ALT2
WALL TYPE = SOLID
BARREL SPACING = 27"

BACKFILL DETAILS
WIDTH AT ENDS = 12"
ABOVE PIPE = 0"
WIDTH AT SIDES = 12"
BELOW PIPE = 0"



NOTES

- ALL RISER AND STUB DIMENSIONS ARE TO CENTERLINE. ALL ELEVATIONS, DIMENSIONS, AND LOCATIONS OF RISERS AND INLETS SHALL BE VERIFIED BY THE ENGINEER OF RECORD PRIOR TO RELEASING FOR FABRICATION.
ALL FITTINGS AND REINFORCEMENT COMPLY WITH ASTM A996.
ALL RISERS AND STUBS ARE 2 1/2" x 1/2" CORRUGATION AND 1/4" GAGE UNLESS OTHERWISE NOTED.
RISERS TO BE FIELD TRIMMED TO GRADE.
QUANTITY OF PIPE SHOWN DOES NOT PROVIDE EXTRA PIPE FOR CONNECTING THE SYSTEM TO EXISTING PIPE OR DRAINAGE STRUCTURES. OUR SYSTEM IS DETAILED PROVIDING NOMINAL INLET AND/OR OUTLET PIPE STUB FOR CONNECTION TO EXISTING DRAINAGE FACILITIES. IF ADDITIONAL PIPE IS NEEDED IT IS THE RESPONSIBILITY OF THE CONTRACTOR.
HAND TYPE TO BE DETERMINED UPON FINAL DESIGN.
THE PROJECT SUMMARY IS REFLECTIVE OF THE DYODS DESIGN, QUANTITIES ARE APPROX. AND SHOULD BE VERIFIED UPON FINAL DESIGN AND APPROVAL. FOR EXAMPLE, TOTAL EXCAVATION DOES NOT CONSIDER ALL VARIABLES SUCH AS SHORING AND ONLY ACCOUNTS FOR MATERIAL WITHIN THE ESTIMATED EXCAVATION FOOTPRINT.
THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.



ASSEMBLY SCALE: 1" = 10'

DYO48754 School Bell Childcare Underground Detention System Howell, MI DETENTION SYSTEM

Table with columns: PROJECT NO., SEQ. NO., DATE, DESIGNED, CHECKED, APPROVED, SHEET NO.

Table with columns: DATE, REVISION DESCRIPTION, BY




Table with columns: PIPE SPAN, INCHES; AXLE LOADS (kips); MINIMUM COVER (FT)

MINIMUM COVER MAY VARY, DEPENDING ON LOCAL CONDITIONS. THE CONTRACTOR MUST PROVIDE THE ADDITIONAL COVER REQUIRED TO AVOID DAMAGE TO THE PIPE. MINIMUM COVER IS MEASURED FROM THE TOP OF THE PIPE TO THE TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE.

CONSTRUCTION LOADING DIAGRAM SCALE: N.T.S.

SCOPE: THIS SPECIFICATION COVERS THE MANUFACTURE AND INSTALLATION OF THE DESIGNED DETENTION SYSTEM DETAILED IN THE PROJECT PLANS.
MATERIAL: THE MATERIAL SHALL CONFORM TO THE APPLICABLE REQUIREMENTS LISTED BELOW.
ALUMINIZED TYPE 2 STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-274 OR ASTM A-92.
THE GALVANIZED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-218 OR ASTM A-929.
THE POLYMER COATED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-246 OR ASTM A-742.
THE ALUMINUM COILS SHALL CONFORM TO THE APPLICABLE REQUIREMENTS OF AASHTO M-197 OR ASTM B-744.
CONSTRUCTION LOADS: CONSTRUCTION LOADS MAY BE HIGHER THAN FINAL LOADS. FOLLOW THE MANUFACTURER'S OR NSCPA GUIDELINES.
NOTE: THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.




ASSEMBLY SCALE: 1" = 10'

DYO48754 School Bell Childcare Underground Detention System Howell, MI DETENTION SYSTEM


Table with columns: PROJECT NO., SEQ. NO., DATE, DESIGNED, CHECKED, APPROVED, SHEET NO.

Table with columns: DATE, REVISION DESCRIPTION, BY



REINFORCING TABLE

Table with columns: DIA CMP RISER, A, B, REINFORCING, BEARING PRESSURE (PSF)



ROUND OPTION PLAN VIEW

- NOTES:
1. DESIGN IN ACCORDANCE WITH AASHTO, 17th EDITION.
2. DESIGN LOAD HS25.
3. EARTH COVER = 1' MAX.
4. CONCRETE STRENGTH = 3,500 psi
5. REINFORCING STEEL = ASTM A615, GRADE 60.
6. PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.
7. TRIM OPENING WITH DIAGONAL #4 BARS. EXTEND BARS A MINIMUM OF 12" BEYOND OPENING. BEND BARS AS REQUIRED TO MAINTAIN BAR COVER.
8. PROTECTION SLAB AND ALL MATERIALS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.
9. DETAIL DESIGN BY DELTA ENGINEERING, BINGHAMTON, NY.

MANHOLE CAP DETAIL SCALE: N.T.S.






Table with columns: DATE, REVISION DESCRIPTION, BY




ASSEMBLY SCALE: 1" = 10'

DYO48754 School Bell Childcare Underground Detention System Howell, MI DETENTION SYSTEM

Table with columns: PROJECT NO., SEQ. NO., DATE, DESIGNED, CHECKED, APPROVED, SHEET NO.

Table with columns: DATE, REVISION DESCRIPTION, BY

TABLE 1: Table with columns: DIAMETER, D; MIN COVER; CORR. PROFILE



- INSTALLATION NOTES:
1. WHEN PLACING THE FIRST LIFTS OF BACKFILL IT IS IMPORTANT TO MAKE SURE THAT THE BACKFILL IS PROPERLY COMPACTED UNDER AND AROUND THE PIPE HAUNCHES.
2. OTHER ALTERNATE BACKFILL MATERIAL MAY BE ALLOWED DEPENDING ON SITE SPECIFIC CONDITIONS, AS APPROVED BY SITE ENGINEER.
3. BACKFILL USING CONTROLLED LOW-STRENGTH MATERIAL (CLSM, "FLASH FILL" OR "FLOWABLE FILL") MAY BE USED WHEN THE SPACING BETWEEN THE PIPES WILL NOT ALLOW FOR PLACEMENT AND ADEQUATE COMPACTION OF THE BACKFILL. CONTACT CONTECH FOR FURTHER EVALUATION.
4. IF SALTING AGENTS FOR SNOW AND ICE REMOVAL ARE USED ON OR NEAR THE PROJECT, A GEOMEMBRANE BARRIER IS RECOMMENDED OVER THE UPPER HALF OF THE PIPE. THE GEOMEMBRANE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM A CHANGE IN THE SURROUNDING ENVIRONMENT OVER A PERIOD OF TIME. PLEASE REFER TO THE CORRUGATED METAL PIPE DETENTION DESIGN GUIDE FOR ADDITIONAL INFORMATION.

TABLE 2: SOLID STANDARD CMP DETENTION AND CMP DRAINAGE STANDARD BACKFILL SPECIFICATIONS

Table with columns: MATERIAL LOCATION, MATERIAL SPECIFICATION, DESCRIPTION

- NOTES:
FOR MULTIPLE BARREL INSTALLATIONS, THE RECOMMENDED STANDARD SPACING BETWEEN PARALLEL PIPE RUNS SHALL BE THE PIPE DIAMETER / 2 BUT NO LESS THAN 12" FOR DIAMETERS < 12"; FOR 12" AND LARGER DIAMETERS, THE MINIMUM SPACING IS 36". CONTACT YOUR CONTECH REPRESENTATIVE FOR NONSTANDARD SPACING.
APPROVED REGIONAL EQUIVALENTS FOR SECTION 5A INCLUDE CA-7, C000T #87, MIDOT 26, 34G, OR 21AA STONE OR GRAVEL; #87, MIDOT 6A, 23, 3G, 34G.

MANUFACTURER RECOMMENDED BACKFILL



DYO48754 School Bell Childcare Underground Detention System Howell, MI DETENTION SYSTEM


Table with columns: PROJECT NO., SEQ. NO., DATE, DESIGNED, CHECKED, APPROVED, SHEET NO.

CMP DETENTION INSTALLATION GUIDE

PROPER INSTALLATION OF A FLEXIBLE UNDERGROUND DETENTION SYSTEM WILL ENSURE LONG-TERM PERFORMANCE. THE CONFIGURATION OF THESE SYSTEMS OFTEN REQUIRES SPECIAL CONSTRUCTION PRACTICES THAT DIFFER FROM CONVENTIONAL FLEXIBLE PIPE CONSTRUCTION. CONTECH ENGINEERED SOLUTIONS STRONGLY SUGGESTS HOLDING A PRE-CONSTRUCTION MEETING WITH YOUR LOCAL SALES ENGINEER TO DETERMINE IF ADDITIONAL MEASURES, NOT COVERED IN THIS GUIDE, ARE APPROPRIATE FOR YOUR SITE.


FOUNDATION

CONSTRUCT A FOUNDATION THAT CAN SUPPORT THE DESIGN LOADING APPLIED BY THE PIPE AND ADJUSTABLE BACKFILL WEIGHT AS WELL AS MAINTAIN ITS INTEGRITY DURING CONSTRUCTION.
IF SOFT OR UNSUITABLE SOILS ARE ENCOUNTERED, REMOVE THE POOR SOILS DOWN TO A SUITABLE DEPTH AND THEN BUILD UP TO THE APPROPRIATE ELEVATION WITH A COMPACTED BACKFILL MATERIAL. THE STRUCTURAL FILL MATERIAL GRADATION SHOULD NOT ALLOW THE MIGRATION OF FINES, WHICH CAN CAUSE SETTLEMENT OF THE DETENTION SYSTEM OR PAVEMENT ABOVE. IF THE STRUCTURAL FILL MATERIAL IS NOT COMPATIBLE WITH THE UNDERLYING SOILS AN ENGINEERING FABRIC SHOULD BE USED AS A SEPARATOR. IN SOME CASES, USING A STIFF REINFORCING GEOTEXTILE REDUCES OVER EXCAVATION AND REPLACEMENT FILL QUANTITIES.




GEOMEMBRANE BARRIER

A SITE'S RESISTIVITY MAY CHANGE OVER TIME WHEN VARIOUS TYPES OF SALTING AGENTS ARE USED, SUCH AS ROAD SALTS FOR DEICING AGENTS. IF SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE, A GEOMEMBRANE BARRIER IS RECOMMENDED WITH THE SYSTEM. THE GEOMEMBRANE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM THE USE OF SUCH AGENTS INCLUDING PREMATURE CORROSION AND REDUCED ACTUAL SERVICE LIFE.
THE PROJECT'S ENGINEER OF RECORD IS TO EVALUATE WHETHER SALTING AGENTS WILL BE USED ON OR NEAR THE PROJECT SITE, AND USE HIS/HER BEST JUDGMENT TO DETERMINE IF ANY ADDITIONAL PROTECTIVE MEASURES ARE REQUIRED. BELOW IS A TYPICAL DETAIL SHOWING THE PLACEMENT OF A GEOMEMBRANE BARRIER FOR PROJECTS WHERE SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE.




BACKFILL PLACEMENT

MATERIAL SHALL BE WORKED INTO THE PIPE HAUNCHES BY MEANS OF SHOVEL-SLICING, RODDING, AIR TAMPER, VIBRATORY ROD, OR OTHER EFFECTIVE METHODS.
IF AASHTO T99 PROCEDURES ARE DETERMINED INFEASIBLE BY THE GEOTECHNICAL ENGINEER OF RECORD, COMPACTION IS CONSIDERED ADEQUATE WHEN NO FURTHER YIELDING OF THE MATERIAL IS OBSERVED UNDER THE COMPACTOR, OR UNDER FOOT, AND THE GEOTECHNICAL ENGINEER OF RECORD (OR REPRESENTATIVE THEREOF) IS SATISFIED WITH THE LEVEL OF COMPACTION.



CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.



ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION, POTENTIALLY CAUSING FLOATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.




IN-SITU TRENCH WALL

IF EXCAVATION IS REQUIRED, THE TRENCH WALL NEEDS TO BE CAPABLE OF SUPPORTING THE LOAD THAT THE PIPE SHEDS AS THE SYSTEM IS LOADED. IF SOILS ARE NOT CAPABLE OF SUPPORTING THESE LOADS, THE PIPE CAN DEFLECT. PERFORMANCE A SIMPLE SOIL PRESSURE CHECK USING THE APPLIED LOADS TO DETERMINE THE LIMITS OF EXCAVATION BEYOND THE SPRING LINE OF THE OUTER MOST PIPES.
IN MOST CASES THE REQUIREMENTS FOR A SAFE WORK ENVIRONMENT AND PROPER BACKFILL PLACEMENT AND COMPACTION TAKE CARE OF THIS CONCERN.



CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.




ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION, POTENTIALLY CAUSING FLOATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.




CMP DETENTION SYSTEM INSPECTION AND MAINTENANCE

UNDERGROUND STORMWATER DETENTION AND INFILTRATION SYSTEMS MUST BE INSPECTED AND MAINTAINED AT REGULAR INTERVALS FOR PURPOSES OF PERFORMANCE AND LONGEVITY.
INSPECTION: INSPECTION IS THE KEY TO EFFECTIVE MAINTENANCE OF CMP DETENTION SYSTEMS AND IS EASILY PERFORMED. CONTECH RECOMMENDS ONGOING, ANNUAL INSPECTIONS. SITES WITH HIGH TRASH LOAD OR SMALL OUTLET CONTROL ORIFICES MAY NEED MORE FREQUENT INSPECTIONS. THE RATE AT WHICH THE SYSTEM COLLECTS POLLUTANTS WILL DEPEND MORE ON SITE SPECIFIC ACTIVITIES RATHER THAN THE SIZE OR CONFIGURATION OF THE SYSTEM.
INSPECTIONS SHOULD BE PERFORMED MORE OFTEN IN EQUIPMENT WASHDOWN AREAS. IN CLIMATES WHERE SANDING AND/OR SALTING OPERATIONS TAKE PLACE, AND IN OTHER VARIOUS INSTANCES IN WHICH ONE WOULD EXPECT HIGHER ACCUMULATIONS OF SEDIMENT OR ABRASIVE/ CORROSIVE CONDITIONS, A RECORD OF EACH INSPECTION IS TO BE MAINTAINED FOR THE LIFE OF THE SYSTEM.
MAINTENANCE: CMP DETENTION SYSTEMS SHOULD BE CLEANED WHEN AN INSPECTION REVEALS ACCUMULATED SEDIMENT OR TRASH IS CLOGGING THE DISCHARGE ORIFICE.
ACCUMULATED SEDIMENT AND TRASH CAN TYPICALLY BE EVACUATED THROUGH THE MANHOLE OVER THE OUTLET ORIFICE. IF MAINTENANCE IS NOT PERFORMED AS RECOMMENDED, SEDIMENT AND TRASH MAY ACCUMULATE IN FRONT OF THE OUTLET ORIFICE. MANHOLE COVERS SHOULD BE SECURELY SEATED FOLLOWING CLEANING ACTIVITIES. CONTECH DESIGN TECHS THAT ALL SYSTEMS BE DESIGNED WITH AN ACCESS/INSPECTION MANHOLE SITUATED AT OR NEAR THE INLET AND THE OUTLET ORIFICE. SHOULD IT BE NECESSARY TO GET INSIDE THE SYSTEM TO PERFORM MAINTENANCE ACTIVITIES, ALL APPROPRIATE PRECAUTIONS REGARDING CONFINED SPACE ENTRY AND OSHA REGULATIONS SHOULD BE FOLLOWED.
ANNUAL INSPECTIONS ARE BEST PRACTICE FOR ALL UNDERGROUND SYSTEMS. DURING THIS INSPECTION, IF EVIDENCE OF SALTING-IONIC AGENTS IS OBSERVED WITHIN THE SYSTEM, IT IS BEST PRACTICE FOR THE SYSTEM TO BE RINSED, INCLUDING ABOVE THE SPRING LINE SOON AFTER THE SPRING THAW AS PART OF THE MAINTENANCE PROGRAM FOR THE SYSTEM.
MAINTAINING AN UNDERGROUND DETENTION OR INFILTRATION SYSTEM IS EASIEST WHEN THERE IS NO FLOW ENTERING THE SYSTEM. FOR THIS REASON, IT IS A GOOD IDEA TO SCHEDULE THE CLEANOUT DURING DRY WEATHER.
THE FOREGOING INSPECTION AND MAINTENANCE EFFORTS HELP ENSURE UNDERGROUND PIPE SYSTEMS USED FOR STORMWATER STORAGE CONTINUE TO FUNCTION AS INTENDED BY IDENTIFYING RECOMMENDED REGULAR INSPECTION AND MAINTENANCE PRACTICES. INSPECTION AND MAINTENANCE RELATED TO THE STRUCTURAL INTEGRITY OF THE PIPE OR THE SOUNDNESS OF PIPE JOINT CONNECTIONS IS BEYOND THE SCOPE OF THIS GUIDE.




CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.



ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION, POTENTIALLY CAUSING FLOATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.





CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.



ADDITIONAL CONSIDERATIONS




























BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION, POTENTIALLY CAUSING FLOATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.



BOSS Engineering
Engineers Surveyors Planners Landscape Architects
3121 E. GRAND RIVER AVE.
HOWELL, MI. 48843
517.546.4836 FAX 517.548.1670

SCHOOL BELL CHILDCARE
PROJECT
PREPARED FOR
SCHOOL IN THE PINES INC. dba SCHOOL BELL CHILDCARE
4501 WEST HIGHLAND ROAD
MIFLOOD, MI 48868
248.830.9542

Table with columns: PROJECT, TITLE, REVISION, PER, DATE



NOTE:

WHILE PERFORMING WORK INVOLVING GROUNDS MAINTENANCE AND/OR THE CONSTRUCTION/MAINTENANCE OF ANY INFRASTRUCTURE, INCLUDING ROADS, WATER MAINS, SANITARY SEWERS, STORM DRAINS AND STORM WATER BEST MANAGEMENT PRACTICES (BMPs), CONTRACTORS SHALL MINIMIZE POLLUTION FROM STORM WATER RUNOFF THAT CAN AFFECT WATER QUALITY RELATED TO WORK ACTIVITIES. POLLUTANTS THAT COULD IMPAIR WATER QUALITY MAY INCLUDE FUEL, GREASE AND OIL, NUTRIENTS, BACTERIA AND PATHOGENS, LITTER AND DEBRIS, AND SOIL EROSION AND SEDIMENTATION. APPLICABLE BMPs SHALL BE IMPLEMENTED BY THE CONTRACTOR TO THE MAXIMUM EXTENT PRACTICABLE TO PROTECT WATER QUALITY AND WILDLIFE HABITAT.

SOIL EROSION AND SEDIMENTATION CONTROL DETAILS

REVISION BLOCK

NO.	DATE	DESCRIPTION
1	01/01/01	ISSUED FOR BIDDING
2	01/01/01	ISSUED FOR BIDDING
3	01/01/01	ISSUED FOR BIDDING
4	01/01/01	ISSUED FOR BIDDING

ORG. DATE: 01/01/01

SCALE: NONE

DESIGNED BY: WRC


DRAWN BY: Mapping

ONE PUBLIC WORKS DRIVE, BLDG. 66 WEST WATERLOO, MISSOURI 64080-1007


SHEET NO.: 1 of 1

- CONCRETE NOTES:**
1. ALL READY MIX CONCRETE SHALL CONFORM TO A.S.T.M. C 14.
 2. MEASURING, MIXING, TRANSPORTING, AND PLACING OF ALL CONCRETE SHALL COMPLY W/ ACI 304R-02.
 3. ALL REINFORCING BARS, DOUBELS, ANCHOR BOLTS AND ANY INBERTS SHALL BE SECURED IN POSITION PRIOR TO PLACING OF CONCRETE.
 4. AIR ENTRAINED CONCRETE SHALL BE USED FOR ALL SIDEWALKS, PAVING, PLATFORMS, CURBS, AND ALL CONCRETE ELEMENTS EXPOSED TO THE WEATHER.
 5. ALL CONCRETE SHALL DEVELOP THE FOLLOWING COMPRESSIVE STRENGTHS AT 28 DAYS (MIN.):


INTERIOR CONCRETE SLABS	= 4000 PSI
EXTERIOR CONCRETE SLABS	= 4000 PSI
FOOTINGS AND FOUNDATION WALLS	= 3000 PSI
 6. LOCATE ALL SLEEVES, OPENINGS, EMBEDDED ITEMS, ETC., WHICH ARE INDICATED ON ALL DESIGN DRAWINGS. CHECK WITH ALL TRADES TO VERIFY THAT ALL SLEEVES, OPENINGS, AND EMBEDDED ITEMS ARE IN PLACE AND LOCATED CORRECTLY PRIOR TO PLACING THE ADJACENT CONCRETE.
 7. THE SURFACE OF ALL CONSTRUCTION JOINTS SHALL BE CLEANED TO REMOVE ALL DUST, CHIPS OR OTHER FOREIGN MATTER PRIOR TO PLACING THE ADJACENT CONCRETE.
 8. ALL SLABS SHALL BE CURED AND SEALED TO MINIMIZE SHRINKAGE CRACKING.
 9. REFER TO ARCHITECTURAL DRAWINGS FOR MOLDS, GROOVES, ORNAMENTS, OR ACCESSORIES REQUIRED TO BE CAST IN CONCRETE AND FOR LOCATIONS OF FLOOR FINISHES AND SLAB DEPRESSIONS.
 10. PIPES MAY PASS THROUGH STRUCTURAL CONCRETE IN SLEEVES, BUT SHALL NOT BE EMBEDDED THEREIN. SLEEVES SHALL BE WRAPPED WITH EXPANSION JOINT FILLER MATERIAL TO ALLOW CONCRETE TO CURE WITHOUT RESTRAINT. PIPES OR CONDUITS EXCEEDING ONE THIRD THE SLAB OR WALL THICKNESS SHALL NOT BE IN STRUCTURAL CONCRETE UNLESS SPECIFICALLY DETAILED. SEE MECHANICAL AND/OR ELECTRICAL DRAWINGS FOR LOCATIONS OF SLEEVES, ACCESSORIES, ETC.
 11. SLAB SURFACES SHALL BE SMOOTH AND LEVEL OR SHALL HAVE SMOOTH EVEN SLOPE. CONCRETE FINISH SHALL BE SMOOTH FOR INTERIOR FLOOR SLABS AND BROOKE FOR EXTERIOR WALKS.
 12. DURING COLD WEATHER MONTHS, ALL CONCRETE SHALL COMPLY W/ ACI COLD WEATHER CONCRETING AC 308R-11. PER ACI COLD WEATHER IS DEFINED AS A PERIOD WHEN FOR MORE THAN 15) CONSECUTIVE DAYS, THE FOLLOWING CONDITIONS MUST EXIST:
 - 1) THE AVERAGE DAILY AIR TEMP IS LESS THAN 40 F. AND,
 - 2) THE AIR TEMP IS NOT GREATER THAN 50 F FOR MORE THAN 50 F THAN ONE-HALF OF ANY 124-HR PERIOD.
 13. DURING WARM WEATHER MONTHS, ALL CONCRETE SHALL COMPLY W/ ACI COLD WEATHER CONCRETING, AC 308R-11.
- GENERAL NOTES:**
1. FASTENERS AND CONNECTORS, INCLUDING NUTS AND WASHERS, IN CONTACT WITH PRESERVATIVE TREATED WOOD SHALL BE OF HOT-DIPPED, ZINC COATED GALVANIZED STEEL.
 2. CONTINUOUS HORIZONTAL REBAR LAP TO BE A MINIMUM OF 24"
- SOIL BEARING CAPACITY, 1000 PSF (VERIFY)**
AS INDICATED IN THE SOILS REPORT, ALL INTERIOR AND EXTERIOR LOAD BEARING FOOTINGS SHALL BE ENGINEERED TO BEAR ON ALL SOILS CONTAINING A SIGNIFICANT AMOUNT OF ORGANIC SUBSTANCES OR EXCESSIVELY WEAK SOILS. THE DESIGNER HAS CONDUCTED VISUAL INSPECTIONS AND TESTS THAT MAY BE REQUIRED TO PLACE FOOTINGS AT SOME LOCATIONS. ALL ENGINEERING SHALL BE AS INDICATED IN THE SOILS REPORT. IT IS RECOMMENDED THAT THE DESIGNER AND ASSOCIATES BE RETAINED TO OBSERVE THE SOILS IN THE FOOTING EXCAVATIONS PRIOR TO OBSERVING THE REQUIRED BEARING CAPACITY SO THEY CAN TEST THE SOILS FOR THE




FOUNDATION PLAN
SCALE: 1/8" = 1'-0"




FOUNDATION DETAIL 1
SCALE: 1/2" = 1'-0"



FOUNDATION DETAIL 2
SCALE: 1/2" = 1'-0"




SLAB CONTROL JOINT AND CONSTRUCTION JOINT DETAIL 1
SCALE: NONE




DET. @ ALT. TRENCH FTG.
SCALE: 1/2" = 1'-0"

The ideas and design concepts expressed herein and the graphically displayed arrangement of the components represented by this drawing have been developed for the exclusive use of the specified project and are the sole property of the architect. Any conveyance or disclosure of the ideas or design concepts or use of any graphically displayed arrangements of their components shall be at the discretion of and only through the expressed written consent of the Petkoski Architects, L.L.C.
© PETKOSKI ARCHITECTS, L.L.C.

issue / revision	
Drawn by	JN/BG
Checked by	GP
Date	5-18-2024
Scale	AS NOTED
Project No.	24-010
Sheet No.	A-1






FLOOR PLAN
SCALE: 1/8" = 1'-0"

FIRE RATING NOTES:

- INTERIOR DOORS TO BE RATED PER DOOR SCHEDULE, INTERIOR WINDOWS TO BE RATED PER WINDOW SCHEDULE
- ALL UL ASSEMBLIES SPECIFIC CONSTRUCTION CRITERIA CAN BE OBTAINED AND PRINTED FROM UL'S WEB SITE.
- ALL PENETRATIONS SHALL BE SEALED TIGHT WITH AN APPROVED FIRE CAULKING.
- PROVIDE FIRE DAMPERS AND SMOKE DAMPERS PER MECHANICAL PLAN WHERE INDICATED
- ALL FIRE RATED AND SMOKE BARRIER WALLS WILL BE MARKED AND LABELED ABOVE THE CEILING AND OR ATTIC SPACING 301 FOOT INTERVALS AND 64 FEET FROM EACH END OF THE WALL. LETTERING HEIGHT TO BE 3 MINIMUM AND WIDTH OF 3/8 MIN. SUGGESTED WORDING FIRE AND/OR SMOKE BARRIER & PROTECT ALL OPENINGS



FIRE EXTINGUISHER LEGEND

- REC 10# ABC FIRE EXTINGUISHER IN RECESSED CABINET
- FE-1 5# ABC FIRE EXTINGUISHER (MECHANICAL ROOM ONLY)
- FE-2 'K' STYLE FIRE EXTINGUISHER (KITCHEN)

The ideas and design concepts expressed herein and the graphically displayed arrangement of the components represented by this drawing have been developed for the exclusive use of the specified project and are the sole property of the architect. Any conveyance or disclosure of the ideas or design concepts or use of any graphically displayed arrangements of their components shall be at the discretion of and only through the expressed written consent of the Petkoski Architects, L.L.C.

PETKOSKI ARCHITECTS, L.L.C.

issue / revision

Drawn by **JN/BG**

Checked by **GP**

Date **5-18-2024**

Scale **AS NOTED**


Project No. **24-010**

Sheet No. **A-2**




NOTE:

PLUMBING AND HVAC VENTS SHALL BE GROUPED IN ATTIC TO LIMIT THE NUMBER OF ROOF PENETRATIONS. ALL ROOF PENETRATIONS SHALL OCCUR TO THE REAR.




ELEVATION - NORTH

1/8" = 1'-0"




ELEVATION - EAST

1/8" = 1'-0"



ELEVATION - WEST

1/8" = 1'-0"



ELEVATION - SOUTH

1/8" = 1'-0"

The ideas and design concepts expressed herein and the graphically displayed arrangement of the components represented by this drawing have been developed for the exclusive use of the specified project and are the sole property of the architect. Any conveyance of disclosure of the ideas or design concepts or use of any graphically displayed arrangements of their components shall be at the discretion of and only through the expressed written consent of the Petkoski Architects, L.L.C.

© PETKOSKI ARCHITECTS, L.L.C.

issue / revision

Drawn by **JN/BG**

Checked by **GP**

Date **5-18-2024**

Scale **AS NOTED**

Project No. **24-010**

Sheet No. **A-3**



ROOF STRUCTURE NOTES

1. REFER TO COVER SHEET FOR MINIMUM GROUND SNOW LOADING FOR ROOF TRUSSES
2. ROOF TRUSS DESIGN SHALL BE PERFORMED BY A REGISTERED ENGINEER IN THE STATE OF MICHIGAN
3. CONTRACTOR SHALL PROVIDE FINAL TRUSS SHOP DRAWING TO THE ARCHITECT AND THE BUILDING DEPARTMENT FOR REVIEW AND CORRECT. PLAN COPIES SUBMITTED TO BUILDING DEPARTMENT SHALL BE SEALED BY A REGISTERED ENGINEER IN THE STATE OF MICHIGAN
4. CONTRACTOR SHALL PROVIDE ANCHORING AND BRACING FOR ALL ROOF TRUSSES AS REQUIRED BY ROOF TRUSS SHOP DRAWINGS
5. ARCHITECT WILL PROVIDE REQUIRED ADDITIONAL TRUSS BRACING PLAN TO GENERAL CONTRACTOR AFTER BEARING TRUSS SHOP DRAWINGS ARE SUBMITTED TO ARCHITECT
6. CONTRACTOR SHALL VERIFY HEIGHT AND LOCATION OF ALL ROOFTRUSS EQUIPMENT AND SUBMIT TO TRUSS ENGINEER FOR ADEQUATE REINFORCEMENT
7. ALL ROOF TRUSSES SHALL BE CONNECTED TO WALL PLATES USING "IMPSON" H22 BEARING HURRICANE CLIPS AT EACH TRUSS CONNECTION COORDINATE APPROPRIATE TRUSS CONNECTOR WITH TRUSS MANUFACTURER'S SHOP DRAWINGS
8. CONTRACTOR TO VERIFY ALL LOADING WITH TRUSS MANUFACTURER AND ARCHITECT PRIOR TO CONSTRUCTION
9. STRUCTURAL LUMBER SUPPLIER SHALL SUBMIT SHOP DRAWING ON ALL STRUCTURAL LUMBER PRODUCTS INDICATING SIZE, GRADE AND DESIGN STRENGTH TO MEET CONDITIONS INDICATED IN HEADER AND BEAM SCHEDULE. SHOP DRAWING SHALL BE REVISED AND APPROVED BY ARCHITECT PRIOR TO CONSTRUCTION
10. NO DRAFT STOPPING REQUIRED DUE TO SPRINKLER SYSTEM THROUGHOUT BUILDING INCLUDING ATTIC. PER DRAFTSTOPPING EXCEPTION IN MICHIGAN BUILDING CODE IF FIRE SUPPRESSION IS NOT SUPPLIED IN ATTIC, THEN DRAFTSTOPPING IS REQUIRED
1. WATER AND ICE SHIELD SHALL BE APPLIED A MINIMUM OF 2" REARDED HOZ. FROM INSIDE FACE OF OUTSIDE WALLS AT ALL ROOF OVERHANGS AND AT ALL ROOF VALLEYS
2. PROVIDE INSULATED FIRE RATED ATTIC ACCESS DOORS WHEN IN FIRE RATED CEILING - SEE FLOOR PLAN FOR ATTIC ACCESS LOCATIONS. DOORS AND HINGERS, HOOKS AND EYES TO BE PROVIDED BY FRAMING CONTRACTOR
3. COORDINATE DOUBLE AND TRIPLE STUD FRAMING WITH PRE-ENGINEERED GIRDER TRUSS LOCATIONS. REVISE FINAL TRUSS PLANS FOR THESE LOCATIONS AND ANY OTHER ADDITIONAL LOCATIONS AS A RESULT OF TRUSS REVIEW


WOOD HEADERS AND BEAM SCHEDULE

- H-1 5-1/4" x 1-1/2" LSS LSL OR (2) 1-3/4" x 1-1/2" LSS LSL BEAR ON ONE (1) STUD.
- H-2 5-1/4" x 1-1/2" 2.0E LVL OR (2) 1-3/4" x 1-1/2" 2.0E LVL BEAR ON TWO (2) STUDS.
- H-3 5-1/4" x 1-1/8" 2.0E LVL OR (3) 1-3/4" x 1-1/8" 2.0E LVL BEAR ON TWO (2) STUDS.
- H-4 5-1/4" x 1-1/8" 2.0E LVL BEAR ON TWO (2) STUDS.
- H-5 5-1/4" x 1-1/8" 2.0E LVL BEAR ON THREE (3) STUDS.
- B-1 58x21 STEEL BEAM
- C-1 5 x 3 1/2 x 5/8 LINTEL SEE DETAIL

NOTE:
ALL HEADERS TO BE VERIFIED AFTER FINAL TRUSS SHOP DRAWINGS ARE AVAILABLE AND SUBMITTED TO ARCHITECT

NOTE:


TRUSS FABRICATOR TO VERIFY ALL ROOF SLOPE AS INDICATED ON THIS. NOTIFY ARCHITECT OF ANY ADJUSTMENTS TO THE PROPOSED ROOF SLOPES




ROOF PLAN

SCALE: 1/8" = 1'-0"

(ROOF/FRAMING PLAN)




DETAIL SECTION @ BELL TOWER
SCALE: 1/4" = 1'-0"




DETAIL WALL SECTION
SCALE: 1/4" = 1'-0"

BEAM CONNECTION SCHEDULE


BEAM SIZE	NUMBER OF BOLTS AND SIZE	BOLT TYPE	BOLT BEARING TYPE	PILET BILD 1" THICKNESS	SHEAR PLATE THICKNESS
W8x21	(4) 3/4" DIA.	A325	TYPE 1N	1/4"	3/8"



BEAM CONNECTION SINGLE PLATE
SCALE: 1/2" = 1'-0"



WOOD PLATES TO STEEL BEAM
SCALE: 1/2" = 1'-0"



COLUMN & BEAM DETAIL
SCALE: 1/2" = 1'-0"

The ideas and design concepts expressed herein and the graphically displayed arrangements of the components represented by this drawing have been developed for the exclusive use of the specified project and are the sole property of the architect. Any conveyance of disclosure, the ideas or design concepts or use of a graphically displayed arrangements of its components shall be at the discretion of only through the expressed written consent of the Petkoski Architects, L.L.C.

PETKOSKI ARCHITECTS, L.L.C.

issue / revision

Drawn by: JN/BM

Checked by: GF

Date: B-18-2024

Scale: AS NOTED

Project No.: 24-010

Sheet No.:

A-4



[Handwritten signature]



(517) 546-6121
FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

May 08, 2024

Boss Engineering
3121 East Grand River Avenue
Howell, MI 48843

Attention: Jared Prather

Reference: 4501 West Highland Road - Sub-Surface Exploration

Dear Mr. Prather,

Five (05) soil test borings designated as soil boring locations #1 through #5 were drilled in the influence of a planned new building located at 4501 West Highland Road in Highland Charter Township, Michigan. Soil test boring locations #1 and #5 were performed to determine the soil infiltration characteristics of the sub-surface sub-grade materials for a proposed underground detention system. Soil test borings #2 through #4 were performed in the influence of the proposed building to determine the structural integrity of the sub-surface sub-grade materials. Each of the test boring locations were advanced to a depth of twenty feet (20'-0") below the existing site grade. The soil boring locations can be identified on the enclosed diagram.

Soil descriptions and depths shown on the soil boring logs were approximate indications of changes from one soil to another and are not intended to represent an exact geological change or stratification.

Ground water was encountered in some of the test boring locations at the following depths:

Test boring #1 – None

Test boring #2 – None

Test boring #3 – 18'-6" below the existing site grade.

Test boring #4 – 19'-0" below the existing site grade.

Test boring #5 – 19'-0" below the existing site grade.

It should be noted that short-term ground water observations may not provide a reliable indication of the depth of the water table. In cohesive soils this is due to the slow rate of water infiltration into the bore hole as well as the potential for water to be trapped in overlying layers of granular soil in periods of heavy rain fall.

Information obtained from soil blow counts (standard penetration) indicate that the soils are variably compacted. The encountered granular soils were generally in a medium dense state, and the encountered cohesive soils generally had medium stiff to very stiff consistencies.



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

Soil blow counts, profiles and the unconfined compressive strengths of the encountered sub-grade soils can be reviewed on the test boring logs.

Site Preparation

It is anticipated that there will be a minimal amount of fill material required for the site. Prior to the construction of footings or slabs all organic soils or unsuitable fill materials should be removed and it is recommended that the existing sub-grade be uniformly compacted to a minimum density of ninety-five percent of the materials maximum unit weight with a 20 ton vibratory roller. Engineered fill materials could then be placed in horizontal lifts not exceeding one foot in depth with each lift compacted uniformly to a minimum density of ninety-five percent of the materials maximum unit weight as determined by AASHTO T-180 or ASTM D1557. It is anticipated that the granular sub grade soils could be used as engineered fill materials in areas where an MDOT class III granular material is suitable. If any of the on-site cohesive material is re-used as an engineered fill material it is recommended that the material be compacted with a padfoot (sheepsfoot) roller. Hastings Testing Engineers and Environmental Inc. should be on site during excavating and filling operations to verify the suitability of the native sub-grade and proposed engineered fill materials. It is recommended that all existing sub-grade soils be proof rolled with a fully loaded tandem axle dump truck or other approved equipment to determine if there is any sub-grade instability. Any unstable sub-grade materials should be removed and replaced with engineered fill material as described above.

Site Utilities

Temporary excavations for site utilities shallower than twelve feet should be able to use typical benched excavations at a 1.5:1 slope. For site utilities deeper than twelve feet it is recommended that a protective system be utilized such as trench boxes or shoring. The excavating contractor should be prepared for the potential of encountering perched ground water. Any ground water encountered at depths less than nineteen feet should be able to be removed with typical 2" pumps. Special dewatering techniques may be required for utilities placed deeper than the anticipated ground water elevation of approximately nineteen feet (19'-0) below the existing site grade. All temporary excavations should be performed according to OSHA standards and specifications.

The existing granular sub-grade materials could be suitable for backfilling utility trenches where a MDOT Class III granular material is required. The excavating contractor should be prepared to import material for utility trenches requiring MDOT class II granular material.



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

Foundation Recommendation

Based on the project information provided (one story building with slab on grade) and the results of field tests, it is believed that the proposed structure can be supported with conventional spread or strip footings. Prior to the construction of footings or floor slabs all organic soil and unsuitable fill materials should be removed and replaced with engineered fill materials as described in the site preparation portion of the report.

Footings could then be proportioned for a design soil pressure of two thousand pounds per square foot between one foot (1'-0") and ten feet (10'-0") below the existing site grade. Care should be taken to either remove or re-compact any loose granular or cohesive soils found in the bottom of the footing sub-grade locations. All exterior footings should be constructed at or below the maximum frost penetration of three feet six inches (3'-6") below finished grade. All footings and slabs should be constructed on naturally occurring sub-soils or engineered fill materials.

Floor Slab Recommendation

It is recommended that a minimum of six inches of clean coarse granular soil (MDOT class II granular material) be placed under all concrete slabs to provide a capillary break for any moisture migration. It is also recommended that a minimum 10 mil vapor barrier be installed directly under the concrete slab.

Expected Settlement

It is estimated that a properly configured shallow foundation constructed on the naturally occurring sub-grade soil or engineered fill material will have less than one inch of settlement and less than one-half inch of differential settlement.

Seismic Site Class

The known properties of the soils at the site are limited to the explored depths of the borings (20 feet) performed for this evaluation. Based on the conditions encountered in the borings, seismic site Class D applies to this site in accordance with the IBC and Michigan Building Code. The potential for liquefaction of the sub-grade soils should be considered low.

Detention Basin Infiltration

Test boring location #1 and #5 were drilled in the influence of the proposed underground detention system. Hastings Testing Engineers and Environmental Inc. was requested to perform permeability tests from soil sampled during drilling operations. The permeability tests were performed to determine the hydraulic conductivity of existing soils in the influence of the proposed detention pond.



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

Hastings Testing Engineers and Environmental Inc. performed the constant head/falling head permeability tests on five samples (ASTM D2434). The results of the tests are as follows:

Test #1

Sample: Soil boring location #1.

Depth: Approximately four feet below the existing site grade.

Sub-Grade Material: Coarse Brown Sand with Fine Gravel and some Silt

$$K_{sat} = 3.8 \frac{in}{hr}$$

Test #2

Sample: Soil boring location #1.

Depth: Approximately nine feet below the existing site grade.

Sub-Grade Material: Silty Brown Clay

$$K_{sat} = 0.000088 \frac{in}{hr}$$

Test #3

Sample: Soil boring location #1.

Depth: Approximately nineteen feet below the existing site grade.

Sub-Grade Material: Coarse Brown Sand

$$K_{sat} = 8.6 \frac{in}{hr}$$

Test #4

Sample: Soil boring location #5.

Depth: Approximately five feet below the existing site grade.

Sub-Grade Material: Coarse Brown Sand with Fine Gravel and some Silt

$$K_{sat} = 2.0 \frac{in}{hr}$$

Test #5

Sample: Soil boring location #5.

Depth: Approximately seven feet below the existing site grade.

Sub-Grade Material: Silty Brown Clay

$$K_{sat} = 0.000031 \frac{in}{hr}$$



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

Conclusion

Experience indicates that the actual subsoil conditions at the site could vary from those generalized on the basis of the test borings made at specific locations. It is therefore essential that Hastings Testing Engineers and Environmental Inc. be notified of any variation of the soil conditions to determine the effects on the recommendations in this report. The evaluations and recommendations contained in the report have been formulated on assumed data relating to the proposed project. Any significant change in this data in the final design plans should be brought to our attention for review and evaluation.

If you should have further questions, please contact our office.

Sincerely,

Marc A. W. Smith PE





(517) 546-6121
FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
AND ENVIRONMENTAL INC.**


"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

4501 West Highland Road

Soil Boring Testing Diagram

Date : 04/26/2024



● = Approximate Test Location



(517) 546-6121
 FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # : 7029
 CLIENT # : 4562
 DATE : 04/26/24
 PAGE : 1

LOCATION : Soil Boring #1 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
[Pattern]	0.5							
[Pattern]	1.0							
[Pattern]	1.5		4					
[Pattern]	2.0		6					
[Pattern]	2.5	SS1	6	12	4.6			
[Pattern]	3.0							
[Pattern]	3.5		6					
[Pattern]	4.0		7					
[Pattern]	4.5	SS2	6	13	5.1			
[Pattern]	5.0							
[Pattern]	5.5							
[Pattern]	6.0		5					
[Pattern]	6.5		9					
[Pattern]	7.0	SS3	13	22	10.8		9000.	
Type of Sample: SS - Split Spoon SL - Split Spoon With Liner ST - Shelby Tube			* Standard Penetration Test - Driving 2" OD Sampler 18" with 140 # Hammer, Falling 30" Count made at 6" intervals.					
DRILLING METHOD : Track Mounted Auger DRILLING FOREMAN : T. Dingman BACKFILL MATERIAL: Existing Material			GROUND WATER ENCOUNTERED AT : None GROUND WATER AFTER COMPLEATION: None GROUND WATER AFTER :					



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7029
 CLIENT # :4562
 DATE :04/26/24
 PAGE :2

LOCATION :Soil Boring #1 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	7.5							
	8.0							
	8.5		7					
	9.0		7					
	9.5	SS4	12	19	10.4		8000.	
	10.0							
	10.5							
	11.0							
	11.5							
	12.0							
	12.5							
	13.0							
	13.5			9				
	14.0			9				

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :None
 GROUND WATER AFTER COMPLEATION:None
 GROUND WATER AFTER :



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7029
 CLIENT # :4562
 DATE :04/26/24
 PAGE :3

LOCATION :Soil Boring #1 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	14.5	SS5	10	19	11.3		7500.	
	15.0							
	15.5							
	16.0							
	16.5							
	17.0							
	17.5							
	18.0							
Coarse Brown Sand	18.5		6					
	19.0		9					
	19.5	SS6	12	21	5.0			
End Of Soil Boring #1	20.0							

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :None
 GROUND WATER AFTER COMPLEATION:None
 GROUND WATER AFTER :



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7030
 CLIENT # :4562
 DATE :04/26/24
 PAGE :1

LOCATION :Soil Boring #2 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Organic Soil & Material	0.5							
Silty Brown Clay	1.0							
	1.5		4					
	2.0		6					
	2.5	SS1	7	13	14.6		2000.	
	3.0							
Coarse Brown Sand with Fine	3.5		3					
Gravel and some Silt	4.0		5					
	4.5	SS2	9	14	5.3			
	5.0							
	5.5							
	6.0		6					
	6.5		9					
Silty Brown Clay	7.0	SS3	9	18	15.5		2000.	

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :None
 GROUND WATER AFTER COMPLEATION:None
 GROUND WATER AFTER :



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7030
 CLIENT # :4562
 DATE :04/26/24
 PAGE :2

LOCATION :Soil Boring #2 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	7.5							
	8.0							
Coarse Brown Sand	8.5		7					
	9.0		8					
	9.5	SS4	11	19	6.1			
	10.0							
	10.5							
	11.0							
	11.5							
	12.0							
	12.5							
	13.0							
	13.5			6				
	14.0			6				

Type of Sample: SS - Split Spoon * Standard Penetration Test - Driving 2" OD
 SL - Split Spoon With Liner Sampler 18" with 140 # Hammer, Falling 30"
 ST - Shelby Tube Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger GROUND WATER ENCOUNTERED AT :None
 DRILLING FOREMAN :T. Dingman GROUND WATER AFTER COMPLEATION:None
 BACKFILL MATERIAL:Existing Material GROUND WATER AFTER :



(517) 546-6121
 FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7031
 CLIENT # :4562
 DATE :04/26/24
 PAGE :1

LOCATION :Soil Boring #3 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Organic Soil & Material	0.5							
Coarse Brown Sand with Fine Gravel and some Silt	1.0							
	1.5		4					
	2.0		3					
	2.5	SS1	4	7	5.6			
	3.0							
	3.5		4					
	4.0		4					
	4.5	SS2	5	9	6.5			
	5.0							
	5.5							
Silty Brown Clay	6.0		3					
	6.5		8					
	7.0	SS3	6	14	9.9		9000.	

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :18' 6" BEG
 GROUND WATER AFTER COMPLEATION:18' 6" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering

3121 E. Grand River

Howell,

MI 48843

REPORT # :7031

CLIENT # :4562

DATE :04/26/24

PAGE :2

LOCATION :Soil Boring #3 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	7.5							
	8.0							
	8.5		8					
	9.0		8					
	9.5	SS4	12	20	10.1		9000.	
	10.0							
	10.5							
	11.0							
	11.5							
	12.0							
	12.5							
	13.0							
	13.5			5				
	14.0			4				

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :18' 6" BEG
 GROUND WATER AFTER COMPLEATION:18' 6" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7031
 CLIENT # :4562
 DATE :04/26/24
 PAGE :3

LOCATION :Soil Boring #3 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	14.5	SS5	4	8	12.7		5000.	
	15.0							
	16.0							
	16.5							
	17.0							
	17.5							
	18.0							
Coarse Brown Sand	18.5		3					
	19.0		3					
	19.5	SS6	3	6	8.9			
End Of Soil Boring #3	20.0							

Type of Sample. SS Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :18' 6" BEG
 GROUND WATER AFTER COMPLEATION:18' 6" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7032
 CLIENT # :4562
 DATE :04/27/24
 PAGE :1

LOCATION :Soil Boring #4 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Organic Soil & Material	0.5							
Coarse Brown Sand with Fine Gravel and some Silt	1.0							
	1.5		2					
	2.0		5					
	2.5	SS1	5	10	4.5			
	3.0							
	3.5		5					
	4.0		9					
	4.5	SS2	9	18	5.3			
	5.0							
	5.5							
Silty Brown Clay	6.0		8					
	6.5		13					
	7.0	SS3	14	27	8.8		9000.	

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD Sampler 18" with 140 # Hammer, Falling 30" Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :19' 0" BEG
 GROUND WATER AFTER COMPLETION:19' 0" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7032
 CLIENT # :4562
 DATE :04/27/24
 PAGE :2

LOCATION :Soil Boring #4 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	7.5							
	8.0							
	8.5		3					
	9.0		5					
	9.5	SS4	12	17	12.5		7000.	
	10.0							
	10.5							
	11.0							
	11.5							
	12.0							
	12.5							
	13.0							
	13.5			2				
	14.0			4				

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD Sampler 18" with 140 # Hammer, Falling 30" Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :19' 0" BEG
 GROUND WATER AFTER COMPLETION:19' 0" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
3121 E. Grand River
Howell, MI 48843

REPORT # :7032
CLIENT # :4562
DATE :04/27/24
PAGE :3

LOCATION :Soil Boring #4 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Coarse Brown Sand	14.5	SS5	12	16	6.0			
	15.0							
	15.5							
	16.0							
	16.5							
	17.0							
	17.5							
	18.0							
	18.5			2				
	19.0			4				
End Of Soil Boring #4	19.5	SS6	4	8	9.5			
	20.0							
Type of Sample: SS - Split Spoon SL - Split Spoon With Liner ST - Shelby Tube			* Standard Penetration Test - Driving 2" OD Sampler 18" with 140 # Hammer, Falling 30" Count made at 6" intervals.					
DRILLING METHOD :Track Mounted Auger DRILLING FOREMAN :T. Dingman BACKFILL MATERIAL:Existing Material			GROUND WATER ENCOUNTERED AT :19' 0" BEG GROUND WATER AFTER COMPLEATION:19' 0" BEG GROUND WATER AFTER :1 Hour					



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7033
 CLIENT # :4562
 DATE :04/27/24
 PAGE :1

LOCATION :Soil Boring #5 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Organic Soil & Material	0.5							
	1.0							
Coarse Brown Sand with Fine Gravel and some Silt	1.5		2					
	2.0		2					
	2.5	SS1	3	5	4.3			
	3.0							
	3.5		2					
	4.0		4					
	4.5	SS2	4	8	6.6			
	5.0							
	5.5							
	Silty Brown Clay	6.0		3				
6.5			4					
7.0		SS3	6	10	14.9		3000.	
Type of Sample: SS - Split Spoon SL - Split Spoon With Liner ST - Shelby Tube			* Standard Penetration Test - Driving 2" OD Sampler 18" with 140 # Hammer, Falling 30" Count made at 6" intervals.					
DRILLING METHOD :Track Mounted Auger DRILLING FOREMAN :T. Dingman BACKFILL MATERIAL:Existing Material			GROUND WATER ENCOUNTERED AT :19' 0" BEG GROUND WATER AFTER COMPLEATION:19' 0" BEG GROUND WATER AFTER :1 Hour					



(517) 546-6121
 FAX (517) 546-1478

**HASTINGS TESTING ENGINEERS
 AND ENVIRONMENTAL INC.**

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
 3121 E. Grand River
 Howell, MI 48843

REPORT # :7033
 CLIENT # :4562
 DATE :04/27/24
 PAGE :2

LOCATION :Soil Boring #5 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Silty Brown Clay	7.5							
	8.0							
	8.5		3					
	9.0		5					
	9.5	SS4	10	15	11.3		9000.	
	10.0							
	10.5							
	11.0							
	11.5							
	12.0							
	12.5							
	13.0							
	13.5			5				
	14.0			4				

Type of Sample: SS - Split Spoon
 SL - Split Spoon With Liner
 ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
 Sampler 18" with 140 # Hammer, Falling 30"
 Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
 DRILLING FOREMAN :T. Dingman
 BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :19' 0" BEG
 GROUND WATER AFTER COMPLEATION:19' 0" BEG
 GROUND WATER AFTER :1 Hour



(517) 546-6121
FAX (517) 546-1478

HASTINGS TESTING ENGINEERS AND ENVIRONMENTAL INC.

"Testing to keep America on a firm foundation"

4841 GOLF CLUB ROAD • HOWELL, MI 48843

REPORT OF SOIL BORING

TESTED FOR: Boss Engineering
3121 E. Grand River
Howell, MI 48843

REPORT # :7033
CLIENT # :4562
DATE :04/27/24
PAGE :3

LOCATION :Soil Boring #5 - See Enclosed Diagram

Soil Description	Depth in Feet	Sample & Type	Blow Count *	N Val	% Water	Natural WT. P C F	Unconfined Strength	
							Str. PSF	Fail Strain
Coarse Brown Sand	14.5	SS5	10	14	6.7			
	15.0							
	15.5							
	16.0							
	16.5							
	17.0							
	17.5							
	18.0							
	18.5			2				
	19.0			4				
	19.5		SS6	10	14	10.7		
	20.0							
End Of Soil Boring #5								

Type of Sample: SS - Split Spoon
SL - Split Spoon With Liner
ST - Shelby Tube

* Standard Penetration Test - Driving 2" OD
Sampler 18" with 140 # Hammer, Falling 30"
Count made at 6" intervals.

DRILLING METHOD :Track Mounted Auger
DRILLING FOREMAN :T. Dingman
BACKFILL MATERIAL:Existing Material

GROUND WATER ENCOUNTERED AT :19' 0" BEG
GROUND WATER AFTER COMPLETION:19' 0" BEG
GROUND WATER AFTER :1 Hour